

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

For corners in

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

Deborah K. Kellerman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

<u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>14W</u>	<u>M-8 (E 1/4, 24)</u> <u>Polkton Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Donald W. Schiele, in a field survey on November 15, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-8 East 1/4 corner of Section 24, Polkton Twp.

Original Government Corner Record:

Set 1/4 sec post

Post

Sugar 9 in dia bears S79W 17 lk dist.

Do 22 " " " N35W 19 " "

John Mullett, Deputy Surveyor

April 7, 1837

L.C.R.C. recorded in Liber 1, Page 477,

6-23-72

X cut in pavt

36" Maple

N88°E 24.7'

X cut conc headwall

N85°W 17.56'

14" W Cherry

N17°W 92.0'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-8 Found Railroad Spike over "X" in concrete, 11" below gravel road surface, and accepted as a careful and faithful perpetuation of the position of the original corner.

Found chiselled "X" in West end of concrete Headwall

N15°E 60.99'

Found nail in North side of 48" Maple

S86°30'E 34.34'

Found nail in South side of Power Pole

S88°30'W 30.99'

Found chiselled "X" in East end of concrete Headwall

N83°W 17.54'

Found nail in East side of 24" Cherry

N17°W 91.98'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 11/21/94

Maday D. Hedewald



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-8 Removed Railroad Spike and concrete. Set 3/4" X 24" steel bar with Ottawa County Remon Cap, 6" below gravel road surface.

Chiselled "X" in West end of concrete Headwall

N15°E 60.99'

Set Ottawa County Remon Tag & nail in North side of 48" Maple

S86°30'E 34.34'

Set Ottawa County Remon Tag & nail in SW side of 16" Maple

S35°30'E 101.56'

Set Ottawa County Remon Tag & nail in South side of Power Pole

S88°30'W 31.10'

Chiselled "X" in East end of concrete Headwall

N83°W 17.54'

Set Ottawa County Remon Tag & nail in NE side of 14" Maple

N41°W 42.26'

Centerline gravel-surfaced road North & South, 1' West

On occupation line to East

Signed by Donald W. Schiele

Date Nov. 21, 1994

Surveyor's Michigan License No. 23517