

**SURVEY & REMONUMENTATION**

APR 24 1995

OTTAWA COUNTY REMONUMENTATION  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:47

**COMMISSION**

For corners in

Ottawa  
 (County)

Located In:

Corner Code #

- |                                       |                          |                      |
|---------------------------------------|--------------------------|----------------------|
| 1. Public Land Survey                 | T <u>8N</u> R <u>14W</u> | <u>M-11 (NE, 36)</u> |
|                                       | T _____ R _____          | <u>Polkton Twp.</u>  |
|                                       | T _____ R _____          | _____                |
|                                       | T _____ R _____          | _____                |
| 2. Property Controlling in Section    | S _____ T _____ R _____  | _____                |
|                                       | S _____ T _____ R _____  | _____                |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____  | _____                |
|                                       | S _____ T _____ R _____  | _____                |
| 4. Lot No. _____, Recorded Plat _____ |                          |                      |
| 5. Private Claims _____               |                          |                      |

*Phyllis Carlsson*  
 REGISTER OF DEEDS  
 OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, Donald W. Schiele, in a field survey on December 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

M-11 SE corner, Section 25 & NE corner, Section 36, Polkton Twp.  
 Original Government Corner Record: L.C.R.C. recorded in Liber 2, Page 97, 4-5-73  
 Set corner post Sec. 25 & 36 1/2" iron.  
 Post Nail in side T. Pole NW 44.03'  
 Lynn 11 in dia bears S29W 18 lks dist Nail in side P. Pole SW 69.62'  
 Beech 13 " " " N35W 30 " " SW corner hse. fnd. NE 89.93'  
 John Mullett, Deputy Surveyor  
 April 7, 1837

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-11 Found Cast Iron Monument inscribed "Ottawa County Section Corner", 2" below surface in Monument Box, and accepted as a careful and faithful perpetuation of the position of the original corner.  
 SW corner, foundation to House # 4793 N43°E 89.88'  
 Found nail in SE side of Power Pole S43°W 69.68'  
 Found nail & bottle cap in SE side of Power Pole S43°W 69.69'  
 Found nail in East side of Telephone Pole N46°W 44.03'  
 Found nail & bottle cap in East side of Telephone Pole N46°W 44.02'



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-11 Cast Iron Monument inscribed "Ottawa County Section Corner", 2" below surface in Monument Box.  
 SW corner, foundation to House # 4793 N43°E 89.88'  
 North corner, catch basin casting S37°30'E 43.11'  
 Set Ottawa County Remon Tag & nail in NW side of 14" Spruce S45°W 51.83'  
 Set Ottawa County Remon Tag & nail in NE side of Telephone Pole N46°W 44.28'  
 Centerline asphalt road North & South, 0.3' East  
 On centerline asphalt road East  
 Centerline asphalt road West, 2' South

P.A. 345 OTTAWA COUNTY

PEER APPROVED 12/12/94

Signed by Donald W. Schiele

Date DEC. 12, 1994

Surveyor's Michigan License No. 23517