

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

For corners in

Ottawa

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--------------------------|-----------------------------|
| 1. Public Land Survey | T <u>8N</u> R <u>14W</u> | M-12 (E $\frac{1}{4}$, 36) |
| | T _____ R _____ | Polkton Twp. |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

RECORDED

94 DEC 15 AM 11:47

Dorothy Callman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Donald W. Schiele, in a field survey on November 30, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-12 East $\frac{1}{4}$ corner, Section 36, Polkton Twp.

Original Government Corner Record:

L.C.R.C. recorded in Liber 2, Page 379, 11-19-73

Set qr sec post

Set Cast Iron Monument over Stone

Post

Fence Post E. 29.95'

Sugar 10 in dia bears S85W 13 lks

Fence Post W. 33.15'

Do 6 " " " N48W 14 "

John Mullett, Deputy Surveyor

April 7, 1837

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-12 Found Cast Iron Monument inscribed "Ottawa County Section Corner", 3" below surface in Monument Box, and accepted as a careful and faithful perpetuation of the position of the original corner.

Found nail & Tag # 14091 in North side of Fence Post S88°30'E 30.03'

Found PK nail & washer in SE side of Fence Post S54°30'W 40.79'



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-12 Cast Iron Monument inscribed "Ottawa County Section Corner", 3" below surface in Monument Box.

Set Ottawa County Remon Tag & nail in North side of Fence Post S88°30'E 29.93'

Chiselled "X" on North end of 12" Concrete Culvert S20°E 66.62'

Set Ottawa County Remon Tag & nail in SE side of Power Pole S21°30'W 164.29'(E)

Set Ottawa County Remon Tag & nail in SE side of 3" Oak S74°30'W 69.85'

Set Ottawa County Remon Tag & nail in NE side of Power Pole

Centerline asphalt road North & South, 0.2' West

On fence lines East & West

PEER APPROVED 12/12/94

PEER APPROVED

12/12/94

Signed by

Donald W. Schiele

Date

DEC. 12, 1994

Surveyor's Michigan License No.

23517