

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

94 DEC 15 AM 11:47

Deborah Kellman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>14W</u>	<u>M-13 (SE, 36)</u> <u>Polkton Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Donald W. Schiele, in a field survey on November 30, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
M-13 SE corner, Section 36, Polkton Twp.

Original Government Corner Record:
Corner post of Towns 7 & 8 North, 13 & 14 West L.C.R.C. recorded in Liber 2, Page 379,
Post 11-19-73
Sugar 10 in dia bears S54W 10 lks dist 3/4" Pipe in pavement
Do 8 " " " N33W 34 " " C/L street sign W 17.70'
John Mullett, Deputy Surveyor Trans. pole SW 102.60'
March 13, 1837 Tel. pole SE 114.03'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
M-13 Found Cast Iron Monument inscribed "Section Corner", 2" below surface in Monument Box, and accepted as a careful and faithful perpetuation of the position of the original corner.

Found nail in SW side of Power Pole S22°30'E 114.44'
Found nail & disk in NW side of Power Pole S22°30'E 114.07'
Found nail in NE side of Power Pole S24°W 102.64'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-13 Cast Iron Monument inscribed "Section Corner", 2" below surface in Monument Box.
Westerly corner, concrete wingwall to House # 14430 N47°30'E 183.12'(E)
NW corner, foundation to House # 14376 S40°30'E 167.75'(E)
Set Ottawa County Remon Tag & nail in West side of Power Pole S22°30'E 114.44'
Set Ottawa County Remon Tag & nail in East side of Power Pole S24°W 103.03'
Set Ottawa County Remon Tag & nail in East side of Power Pole N13°W 210.38'
Centerline asphalt road North & South, 8' East
On centerline gravel road to East
Field line to West, 18' South

Signed by Donald W. Schiele Date Dec. 12, 1994
Surveyor's Michigan License No. 23517