

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY	34 T. 8 N. 15 R. W.	G-12, H-13	<i>Ottawa Co</i>
2. PROPERTY CONTROLLING IN SECTION	T. S. R. E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.		
4. LOT NO. _____, RECORDED PLAT _____			
5. PRIVATE CLAIMS _____			

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Donald L. Bissell, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

<p>G-12 Dug 2.5' deep in gravel road. Found bottom section of cast iron marker. Raised to 2" below surface with 1" pipe with plastic cap. Witnesses from courthouse missing.</p>	<p>H-13 Found 2" pipe with witnesses from courthouse. Replaced with 4" x 36" conc. monument with alum. cap. 28" R. Oak - S65°E - 87.59' 16" Pin Oak - S40°W - 6.12' 16" Pin Oak - S40°W - 37.00' 12" B. Ash - N22°W - 48.61'</p>
---	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>G-12 1" pipe with plastic cap. S30°E - 64.85' - Power pole N14°W - 120.6' - W. end C.M.P. N9°E - 260.25 - Power pole. In line with row of Willows to West.</p>	<p>H-13 4" x 36" Conc. mon. with alum. cap S40°W - 37.08' - 12" Oak N22°W - 48.71' - 7" Ash S40°W - 6.18' - 14" Oak East - 50.08' - 4" W. Pine S31°E - 47.45' - 8" W. Oak</p>
--	--

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Donald L. Bissell DATE 6-21-83

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

PAGE

PAGE 12

SURVEYOR'S MICHIGAN REGISTRATION NO. 18655

PAGE 12