

SURVEY & REMONUMENTATION

DEC 01 1998

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

SECTION

RECORDED

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8 N</u> R <u>15 W</u>	A-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	SW corner
2. Property Controlling in Section	S _____ T _____ R _____	Section 31
	S _____ T _____ R _____	Crockery Twp
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	Common Corner

98 JUL 24 PM 1:46

Ray Schultz
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Steve Lampen, in a field survey on June 4 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-13 GLO - Britain - 1832 West on South side Sec. 31 67.70 to Grand River where raised mound.	Emmet Peck - found stone - 1907 M-13 to M-12 = 2620 M-12 to M-11 = 2620
GLO - Mullett - 1837 78.20 over Grand River 79.30 intersect range line 20 lks North of temporary 6 mile post and set corner to T7 & 8N. R15 & 16 W. Raised a mound.	Carl T. Bowen - stone - 1954 Survey shows iron on Section line 869 ft South of M-12 Emmet Peck - Survey in Section 6, T7N, R15W A-1 to A-2 = 40.78 ch. A-1 to C-1 = 80.23 ch.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-13 Did not find stone.

Re-established North and South position by measuring M-12 - M-13 equal to M-12 - M-11 as measured by Peck. measure = 2617.95, Peck = 2620

Re-established East and West position by extending M-12 and a found pipe stake 869.5' South of M-12 set by Bowen in 1954. This position measures reasonable with the Peck survey of Section 6, T7N, R15W. See sketch on back.

Set an Ottawa County Remonumentation iron and cap and is accepted as a careful and faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-13 Ottawa County Remonumentation iron and cap

Remonumentation tag in West side	Twin 10"-16" Maple	198°	23.85
Remonumentation tag in West	Twin 16" Ash	343°	68.10
Remonumentation tag in South	Triple 10" Maple	238°	18.27
Remonumentation tag in South	8" Poplar	124°	37.38



Signed by Steven Lampen Date July 20, 1998
Surveyor's Michigan License No. 37279

PA. 345 OF
PEER APPROVED
6-15-98
\$1000 CORNER
Receipt #0175

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1993
ADAPTED FOR WORD PROCESSING MARCH, 1993

SURVEY &
REMONUMENTATION

DEC 01 1998

SECTION



M-11 A-11

MEAS. = 2617.95
PECK = 2620

M-12 A-12

MEAS. = 867.5
BOWEN = 869

180° FOUND PIPE
BY BOWEN-1954

SECTION 36
T8N R16W

MEAS. = 2617.95
PECK = 2620

SECTION 31
T8N R15W

GLO = 79.30 CH. = 5233.8

MEAS. = 5297.24

PECK = 80.23 CH. = 5295.18

M-13 A-13

C-13

M-1 A-1

C-1

SECTION 1
T7N R16W

GLO = 40.20 CH. = 2653.2
MEAS. = 2696
PECK = 40.78 CH. = 2691.48

SECTION 6
T7N R15W

M-2 A-2