

**SURVEY &
REMONUMENTATION**

APR 24 1995

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:52

For corners **COMMISSION**

Doris Kellman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Ottawa (County)	Located In: Crockery Twp.	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>15W</u>	<u>C-4</u>
	T _____ R _____	<u>W 1/4 corner</u>
	T _____ R _____	<u>Section 8</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Carl P. Englert, in a field survey on November 30, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-4 1/4 corner common to Sections 7 & 8
Original Gov't corner set March, 1837
by John Mullett D.S.

LCRC Liber 4, Page 16 (12/11/79)
Set Cast Iron Monument
Inscribed Section Corner
8" Red Oak S.E. 39.02'
6" Red Oak E.N.E. 30.22'
22" Red Oak N.E. 50.02'
S.E. House Cor. N.W. 105.43'

Set Post
Pine 9" S10°W 62 Links
B. Oak 6" N37°E 17 Links

(See Back of Page)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-4 1/4 corner common to Sections 7 & 8

Found 4" Harrison Cast Iron Mon. 6" Deep 4'+/- E. of Road E
Found 18" Oak N.E. 50.12'
found S.E. corner Hse. N.W. 105.43'

OTTAWA COUNTY
PEER APPROVED 12/12/94
Y. P. Nedelco

Accepted as a careful and faithful perpetuation of the original position of the corner.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-4 1/4 corner common to Sections 7 & 8

4" Harrison Cast Iron Mon.
O.C. Remon. Tag & Nail in N.W. side 22" Oak N36°E 50.82'
O.C. Remon. Tag & Nail in S. side 10" Oak N81°W 42.62'
O.C. Remon. Tag & Nail in S.E. side 15" Tw. Oak S30°W 58.82'
O.C. Remon. Tag & Nail in N.E. side 12" Oak S59°E 36.69'

Signed by Carl P. Englert Date 12/5/94
Surveyor's Michigan License No. 18987

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS
REVISED 1975



LCRC Liber 1, Page 267 (2/2/72)
C-4 Found Iron Pipe
Nail in the Face of 16" Oak East 48.81'
Nail in the Face of 18" Oak NE 50.12'
Nail in the Face of 6" Oak SW 39.33'
S.E. House corner NW 105.43'

2007 M
2008 M
2009 M
2010 M
2011 M
2012 M
2013 M
2014 M
2015 M
2016 M
2017 M
2018 M
2019 M
2020 M
2021 M
2022 M