

SURVEY & REMONUMENTATION

APR 24 1995

OTTAWA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:52

For corners **COMMISSION**

Daphne Ballman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

<u>Ottawa</u> <small>(County)</small>	Located In: Crockery Twp.	Corner Code # C-7
1. Public Land Survey	T <u>8N</u> R <u>15W</u>	<u>N.W. Corner</u>
	T _____ R _____	<u>Section 20</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Carl P. Englert, in a field survey on November 23, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
C-7 corner common to Sections 17, 18, 19 & 20
Original gov't corner set March, 1837
by John Mullett

Set Post
Pine 24" S62°E 17 Links
Pine 25" N88°W 65 Links

LCRC Liber 4, Page 275 (12/31/81)
3/4" Steel bar in Mon. Box
P.P. N.E. 62.63'
St. Sign S.E. 55.90'
P.P. S.E. 69.83'
P.P. S.W. 62.63'

(See Back of Page)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
C-7 corner common to Sections 17, 18, 19 & 20
Found 3/4" steel bar in Mon. Box on St. E
Found P.P. S.W. 62.63'
Found P.P. S.E. 69.83'
Found P.P. N.E. 62.63'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94
Harold P. Hedewald

Accepted as a careful and faithful perpetuation of the original position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
C-7 corner common to Sections 17, 18, 19 & 20
Set O.C. Remon Cap on 3/4" Iron Bar in Mon. Box 5" deep
O.C. Remon Tag & Nail in E. Side P.P. S25°W 62.65'
O.C. Remon Tag & Nail in N.E. Side P.P. S36°E 69.86'
O.C. Remon Tag & Nail in S.E. side P.P. N40°E 62.95'
O.C. Remon Tag & Nail in W. Side R.R. tie Sign Post N26°W 55.25'

Signed by Carl P. Englert Jr
Surveyor's Michigan License No. 18987

Date 12/1/94



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

C-7 L.C.R.C. Liber 1, Page 13, (5/4/71)

Fd. Steel Bar in Mon. Box

Nail In P.P. N.E. 62.65'

St. Sign S.E. 55.60'

Nail in 12" Pine S.E. 87.55'

Nail in T.P. S.W. 61.96'

Nail in 14" Maple N.W. 52.01'

1557
3000
3000
3000

100
100
100