

FEB 24 2000

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

99 SEP 23 PM 3:21

For corners in SECTION

Ottawa
(County)

Located In: Crockery Township Corner Code #

- 1. Public Land Survey T8N R 15W D-1
- T R N $\frac{1}{4}$ cor.
- T R Section 5
- T R _____
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

Ray Mullett
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Carl P. Englert, in a field survey on 6-11, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	I
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

D-1 This corner not set by Government Survey, D-13, T9N, R15W
 Set by John Mullett has been held as common to D-1, T8N, R15W
 A Hemlock 6" diameter for 1/4 Sec. Cor. Tree
 LCRC Liber 1023, Page 574, Muskegon County Records, N.C. Jones 9/10/73
 Found Steel Fence Post 1 foot above ground
 N30°E 39.00 6" Cherry Nail & MDSH Tag
 S10°W 44.90' 12" Cherry Nail & MDSH Tag
 N35°W 31.40' 37" Maple Nail & MDSH Tag See Other Side

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-1 Found Steel Fence Post 1'± above grade, set 3/4"x3" Steel Bar with
 Ottawa County Remon Cap
 Found 42" Maple S10°W 45'± to face
 Found 16" Cherry N38°W 31.79'
 Found 18" Aspen N30°E 23.64'
 Measurement from E-1 agrees with Record Distance (See Other Side)
 This Monument is accepted as the best available evidence of the
 position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-1 3/4"x3" Steel Bar with Ottawa County Remon Cap
 O.C. Remon Nail and Tag in N Side 18" Aspen N30°E 23.64'
 O.C. Remon Nail and Tag in E Side 15" Aspen S47°E 25.68'
 O.C. Remon Nail and Tag in W Side 42" Maple S10°W 47.35'
 O.C. Remon Nail and Tag in NE Side 14" Cherry N74°W 29.32'
 O.C. Remon Nail and Tag in NE Side 16" Cherry N38°W 31.79'
 D-1, T9N, R15W held as common to D-13, T9N, R15W

9/13/99
Carl P. Englert
 STATE OF MICHIGAN
 CARL P. ENGLERT
 PROFESSIONAL SURVEYOR
 No. 18987
 18987
 PROFESSIONAL SURVEYOR

Signed by Carl P. Englert
 Surveyor's Michigan License No. 18987

Date 9/13/1999

