

**SURVEY & REMONUMENTATION**

APR 24 1995

**OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

94 DEC 15 AM 11:52

For corners in **COMMISSION**

<u>Ottawa</u> (County)	Located In: <b>Crockery Twp.</b>	Corner Code #: <b>D-3</b>
1. Public Land Survey	T <u>8N</u> R <u>15W</u>	<u>D-3</u>
	T _____ R _____	<u>N. 1/4 Corner</u>
	T _____ R _____	<u>Section 8</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*Richard R. ...*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, Carl P. Englert, in a field survey on December 2, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3		▲										
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

D-3 1/4 corner common to Sections 5 & 8  
Original Gov't corner set March 1837  
by John Mullet D.s.

LCRC Liber 3, Page 224 (11/4/77)  
D-3) Replaced Rubber coated rod with  
Cast Iron Monument Inscribed  
"Ottawa County Section Corner."

Set 1/4 Section Post  
B. Ash 6" N65°W 8 Links  
B. Ash 7" N79°E 18 Links

Ties:  
Concrete Monument S 33.24  
NE Corner House Porch SW 97.54  
Power Pole SW 108.40

See Back of Page

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-3 1/4 corner common to Sections 5 & 8

Found 4" CIM with Broken Top 4" deep 2.5' N of Road E  
Found N. corner House Porch S.W. 97.54'  
Found Conc. Monument S33.24'  
Found P.P. S.W. 108.4'

P.A. 345 OTTAWA COUNTY  
PEER APPROVED 12/12/94

Accepted as a careful and faithful perpetuation of the original position of the corner.

*Andrey P. Nedevell*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


D-3 1/4 corner common to Sections 5 & 8

4" Harrison Cast Iron Mon.  
O.C. Remon. Tag & Nail in S. side P.P.  
O.C. Remon. Tag & Nail in S. side P.P.  
O.C. Remon. Tag & Nail in S.W. side 16" Beech  
Conc. Mon.

N38°W 166.27'  
S72°W 108.43'  
S71°E 58.55'  
South 33.24'

Signed by Carl P. Englert Jr  
Surveyor's Michigan License No. 18987

Date Carl P. 12/5/94



D-3

FD 1/2" Rubber Coated Rob

Elm Stump	SE	18.45'
Concrete Monument	S	33.24'
NE Corner Porch	SW	97.54'
Power Pole	SW	108.40'

7538  
7538  
7538  
7538