

**SURVEY &
REMONUMENTATION**

APR 24 1995

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:49

Phyllis Holman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

<u>Ottawa</u> (County)	Located In: <u>Crockery Twp.</u>	Corner Code # <u>E-3</u>
1. Public Land Survey	T <u>8N</u> R <u>15W</u>	<u>NE Corner</u> <u>Section 8</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Carl P. Englert in a field survey on December 02, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3			▲									
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
E-3 corner common to Sections 4, 5, 8 & 9.
Original Gov't corner set March, 1837
by John Mullet D.S.

LCRC Liber 4, Page 128 (11/11/80)
FD Iron Bar from old Ties
Set Cast Iron Monument
8" Pine SW 30.13
Iron Pipe N 33.00
11" Pine SE 40.34
S. End 30" Conc. Culv SW 43.02

Set Post
Hemlock 9" S89°E 22 Links
B. Ash 8" S44°W 5 Links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
E-3 corner common to Sections 4, 5, 8 & 9
Found 4" Harrison CIM 4" deep in Road $\frac{1}{2}$
Found 8" Pine S.W. 30.13'
Found Iron Pipe North 33.00'
Found 11" Pine S.E. 40.34'
Found S. End 30" Conc. Culvert S.W. 43.02'

Accepted as a careful and faithful perpetuation of the original position of the corner.

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94
Madon D. Nelson

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
E-3 corner common to Sections 4, 5, 8 & 9.

4" Harrison Cast Iron Mon.
O.C. Remon. Tag & Nail in W. side 12" Pine S1°E 28.61'
O.C. Remon. Tag & Nail in S.W. side 14" Pine S20°E 40.23'
 $\frac{1}{2}$ South End 30" Conc. Culvert S69°W 42.77'
S.W. corner Wood Garage N27°E 72.01'

Signed by Carl P. Englert Jr
Surveyor's Michigan License No. 18987

Date 12/5/94



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISION 1-74, 1975
REVISED JAN., 1983