

**SURVEY &
REMONUMENTATION**

APR 24 1995

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

94 DEC 15 AM 11:49

Phyllis Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

<u>Ottawa</u> (County)	Located In: <u>Crockery Twp.</u>	Corner Code #: <u>E-7</u>
1. Public Land Survey	T <u>8N</u> R <u>15W</u>	<u>N.W. Corner</u> <u>Section 21</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Carl P. Englert, in a field survey on November 23, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
E-7 corner common to Sections 16, 17, 21 & 21.
Original Gov't corner set March 1837
by John Mullett

Set Post
Hemlock 30" S42°E 30 Links
Do 13" N17°W 16 Links

L.C.R.C. Liber 1, Page 545, July 1972
Fd. Boat Spike in Mon. Box
N.E. 26.0' Guard Rail Post
S.E. 24.6' Guard Rail Post
S.W. 29.3' Guard Rail Post
N.W. 28.55' Guard Rail Post

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
E-7 corner common to Sections 16, 17, 20 & 21
Found Boat Spike in Mon. Box 3" deep 1'+/- South of St. E
Guard Rail has been reconstructed
Distance checks from North 1/4 corner of Section 20

PA. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94
Wendy D. Mullett

Accepted as a careful and faithful perpetuation of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
E-7 corner common to Sections 16, 17, 20 & 21
Set O.C. Remon. Cap in 3/4" x 2' Iron Bar in Mon. Box 6" deep
O.C. Remon. Tag & Nail in top of Guard Rail Post N45°W 35.70'
O.C. Remon. Tag & Nail in top of Guard Rail Post N60°E 92.10'
O.C. Remon. Tag & Nail in top of Guard Rail Post S40°W 25.10'
O.C. Remon. Tag & Nail in top of Guard Rail Post S70°E 92.63'
P.K. Nail North 16.90'



Signed by Carl P. Englert Jr. Date 12/1/94
Surveyor's Michigan License No. 18987