

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:49

Richard Hillman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

**SURVEY &
REMONUMENTATION**

DEC 05 2000

SECTION _____
Register of Deeds Stamp & File Number

For corners in

<u>Ottawa</u> (County)	Located In: Crockery Twp.	Corner Code # E-8
1. Public Land Survey	T <u>8N</u> R <u>15W</u>	W. 1/4 Corner Section 21
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Carl P. Englert, in a field survey on December 12, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-8 1/4 corner common to Sections 21 & 21
Original Gov't corner set March, 1837
by John Mullet D.S.

LCRC Liber 1, Page 497
Fd. Angle Iron in Stump at Fence Cor.
E. P.P. 16.36'
S.S.E. P.P. 22.87'

Beech 20" 1/4 Section Corner

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-8 1/4 corner common to Sections 21 & 21

Found Angle Iron in stump at fence corner.
Found P.P. East 16.36'
Found P.P. S.S.E. 22.87'

OTTAWA COUNTY
PEER APPROVED 12/12/94


Accepted as a careful and faithful perpetuation of the original position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-8 1/4 corner common to Sections 21 & 21

Set 3/4" x 3' long Iron bar with O.C. Remon. Cap in place of Angle Iron
O.C. Remon. Tag & Nail in E. side P.P. S20°E 22.72'
O.C. Remon. Tag & Nail in S. side P.P. EAST 15.56'
O.C. Remon. Tag & Nail in E. side Ashclump N10°W 22.90'
O.C. Remon. Tag & Nail in N.E. side 4" Cherry N45°W 18.30'

Signed by Carl P. Englert Jr Date 12/12/94
Surveyor's Michigan License No. 18987



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JULY 1971
REVISED JAN. 1983