

SURVEY & REMONUMENTATION

DEC 01 1998

SECTION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Ottawa</u> <small>(County)</small>	Located in:	Corner Code #
1. Public Land Survey	T 8 N R 15 W	E-12
	T _____ R _____	_____
	T _____ R _____	West 1/4 corner
	T _____ R _____	Section 33
2. Property Controlling in Section	S _____ T _____ R _____	Robinson Twp
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECORDED
98 JUL 24 PM 1:45

Ray Johnston
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Steve Lampen, in a field survey on May 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-12 GLO - Brookfield - 1832 North between Sections 32 and 33 40.00 set 1/2 mile post White Oak 40 N 37 E 13 DO 20 N 75 W 20	LCRC L-3 P 374 - VanOrder - 1978 (recorded as F-12) Found 1/2" pipe, set cast iron monument pk in 28" Red Oak SW 53.32 nail in 14" White Oak NW 25.35 pk in 16" Red Oak NNW 28.55 pk in 21" White Oak NNW 50.63
Peck - 1892 Set stake E-12 to E-13 = 2640 E-12 to G-12 = 5252	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-12 Found cast iron monument	28" Red Oak	SW	53.32
E-12 to E-13 measure 2640.7	14" White Oak	NW	25.35
E-12 to G-12 measure 5249.4	16" Red Oak	NNW	28.55


PA 945 OTTAWA COUNTY
DEED APPROVED 6-15-98
S.D.N.

Found cast iron monument is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-12 Cast iron monument
Azimuth = Michigan State Plane Grid Direction

Remonumentation tag in SW side	Twin 20" Oak	341° 06'	28.78
Remonumentation tag in SW side	20" Oak	308° 25'	26.36
Remonumentation tag in SE side	32" Oak	216° 36'	54.42
Remonumentation tag in S side	16" Oak	250° 54'	61.79



Signed by Steven Lampen Date JULY 20, 1998
Surveyor's Michigan License No. 37279

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993