

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

94 DEC 15 AM 11:49

Richard Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

<u>Ottawa</u> (County)	Located In: Crockery Twp.	Corner Code # F-3
1. Public Land Survey	T <u>8N</u> R <u>15W</u>	<u>N 1/4 Corner</u> <u>Section 9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Carl P. Englert, in a field survey on December 02, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-3 1/4 corner common to Sections 4 & 9
Original Gov't corner set March, 1837 by John Mullett D.S.
LCRC Liber 4, Page 128 (11/11/80)
Fd. Angle Iron
Set Cast Iron Monument
Railroad Tie Fence Post South 25.07
Beech 14" S63°E 14 Links 25" Tree ENE 50.77
Beech 11" N 7°W 12 Links 15" Maple NNE 34.72
Power Pole North 50.79

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-3 1/4 corner common to Sections 4 & 9
Found 4" Harrison CIM with broken top 6" deep in road E
Found R.R. tie F. Post South 25.07'
Found 25" Tree ENE 50.77'
Found 15" Maple NNE 34.72'
Found P.P. North 50.79'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94

Accepted as a careful and faithful perpetuation of the original position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-3 1/4 corner common to Sections 4 & 9
4" Harrison Cast Iron Mon. with broken top
O.C. Remon. Tag & Nail in N. side R.R. Tie F.P. S10°W 24.96'
O.C. Remon. Tag & Nail in S. side 28" Ash N72°E 51.31'
O.C. Remon. Tag & Nail in E. side P.P. N 3°W 50.97'
O.C. Remon. Tag & Nail in SW side 12" Birch N72°W 71.21'

Signed by Carl P. Englert
Surveyor's Michigan License No. 18987

Date 12/12/94

