

SURVEY & REMONUMENTATION

APR 24 1995

OTTAWA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:49

For corners of **COMMISSION**

Reginald R. Williams
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Ottawa (County)	Located In: Crockery Twp.	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>15W</u>	<u>F-5</u>
	T _____ R _____	<u>S 1/4 corner</u>
	T _____ R _____	<u>Section 9</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Carl P. Englert in a field survey on November 30, 19 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-5 1/4 corner common to Sections 9 & 16
Original Gov't corner set March 1837
by John Mullet D.S.

LCRC Liber 1, Page 417, May 1972
Found Boat Spike

Set Post
Beech 14" S63°E 14 Links
Beech 11" N7°W 12 Links

Nail in Face of 30" Twin Cherry SE 49.90'
Nail in Face of 10" Pine SW 44.61'
Nail in Face of 46" Maple N 60.33'
Nail in Face of 8" Pine NE 42.83'
⊕ R/W Marker NE 33.13'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-5 1/4 corner common to Sections 9 & 16

Found 3" Harrison Cast Iron Mon. in Mon. Box 4" deep in ⊕ Road
Found S.E. 36" Twin Cherry 49.9+/- (No Nail)
Found N 46" Stump 60.3+/- (No Nail)
Found 15" Pine S.W. 44.6+/- (No Nail)

Accepted as a careful and faithful perpetuation of the original position of the corner.

PA. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94

Harvey D. Medwell

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-5 1/4 corner common to Sections 9 & 16

3" Harrison Cast Iron Mon. in Mon. Box
O.C. Remon. Tag & Nail in N. Side Twin Red Pine
O.C. Remon. Tag & Nail in N.E. Side 10" Red Pine
O.C. Remon. Tag & Nail in S.E. Side 12" Red Pine
O.C. Remon. Tag & Nail in E. Side 36" Tw. Cherry
O.C. Remon. Tag & Nail in S.W. Side 16" Spruce

S58°W 77.77'
N55°W 119.11'
N56°E 48.12'
S 8°E 51.27'
S43°E 40.64'

Signed by Carl P. Englert Jr
Surveyor's Michigan License No. 18987

Date 12/5/94

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28 1987

