

SURVEY & REMONUMENTATION

APR 24 1995

OTTAWA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE

RECORDED

94 DEC 15 AM 11:52

Filing Requirement of Act 74, Mich. P.A. 1970

For corners **COMMISSION**

Politically Robinson Twp.

Daphne Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Ottawa
(County)

Located In: Crockery Twp. Corner Code #

- | | | |
|------------------------------------|--------------------------|---------------------|
| 1. Public Land Survey | T <u>8N</u> R <u>15W</u> | <u>F-13</u> |
| | T ___ R ___ | <u>S 1/4 Corner</u> |
| | T ___ R ___ | <u>Section 33</u> |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Carl P. Englert, in a field survey on December 01, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-13 South 1/4 corner Section 33 set May 1832
by Calvin Britain D.S. LCRC Liber 5, Page 212 (5/17/85)
F-13
Set 1/2 Mile Post Set CIM
W. Ash 30" N29°W 29 Links Robinson Cor. 6.70 East
Pine 20" N31°E 32 Links Tw. Oak NW 31.11
SW 10" Sassafras 9.42
14" Oak SE 20.08

(See back of page)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-13 South 1/4 corner Section 33

Found 4" Harrison CIM
Found SW 10" Sassafras 9.40'
Found TW Oak N.W. 31.11'
Found Robinson Corner 6.70' East
Found 18" Oak S.E. 20.15'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94

Richard D. Hedewell

Accepted as a careful and faithful perpetuation of the original position of the corner.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13 South 1/4 corner Section 33

4" Harrison Cast Iron Monument
O.C. Remon. Tag & Nail in S.E. side 10" Sassafras S50°W 9.40'
O.C. Remon. Tag & Nail in S.W. side 14" Tw. Oak N40°W 31.25'
O.C. Remon. Tag & Nail in N.E. side 18" Oak S30°E 20.11'
O.C. Remon. Tag & Nail in S.E. side 9" Oak N40°E 37.57'
Corner to Town 7 North, Range 15 West East 6.70'

Signed by Carl P. Englert
Surveyor's Michigan License No. 18987

Date 12/5/94



FORM APPROVED BY MICHIGAN STATE BOARD OF SURVEYORS, JAN 26, 1975
REVISED MAY 1983

LCRC Liber 2, Page 405 (11/29/73)

F-13 2" Pipe

N. 6" Oak 22.15'

N.W. 31.05' Tw. Oak

S.E. 20.15' 18" Oak

S.W. 9.4' 10" Sassafras

1973
2000
2000
2000

1973
2000
2000
2000