

**SURVEY &
REMONUMENTATION**

OCT 07 1996

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>OTTAWA</u> (County)	Located In: Crockery Twp.	Corner Code #
1. Public Land Survey	T 8N R 15W	G-2
	T R	W 1/4 corner
	T R	Section 3
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

RECORDED

96 AUG 26 PM 2:01

Robert A. Chastman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Carl P. Englert, Jr., in a field survey on November 16, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5			4	3			2			1
3													
4		7	8			9	10			11			12
5													
6		10	17			16	15			14			13
7													
8		19	20			21	22			23			24
9													
10		30	29			28	27			26			25
11													
12		31	32			33	34			35			36
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-2 1/4 corner common to Sections 3 & 4
Original Government corner set March 1837
by John Mullett
Set 1/4 Section Post
Birch 8" S 38° W 15 links
Birch 6" N 25° E 11 links

LCRC Liber 4, Page 123, 11/14/1980
Found iron bar from old ties
Set cast iron monument
P.P. East 57.84'
Nail in Gate Post NE 43.64'
Nail in Fence Post W. 181.40'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-2 1/4 corner common to Sections 3 & 4
Found 4" cast iron monument with broken top 12" below grade
All witnesses were gone
Found capped iron West 33.00 feet
Found capped iron East 33.00 feet
Distances to G-1 and G-3 agree with record dimensions

P.A. 345 OTTAWA COUNTY
PEER APPROVED 8-20-96
Robert A. Chastman

Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-2 1/4 corner common to Section 3 & 4
4" cast iron monument with broken top 12" below grade 7'± West of centerline of gravel road
Ottawa County Remonumentation tag and nail in N side P.P. N 62° E 65.58'
Ottawa County Remonumentation tag and nail in S side P.P. East 58.32'
Ottawa County Remonumentation tag and nail in W side 8" Maple S 19° E 112.69'
Capped iron West 33.00'
Ottawa County Remonumentation tag and nail in S side P.P. N 80° W 26.80'

Signed by Carl P. Englert Jr.
Surveyor's Michigan License No. 18987

Date 11/20/95

