

1993

OTTAWA COUNTY REMONUMENTATION

RECORDED

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

93 DEC 15 AM 9:31

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
	<u>Crockery Township</u>	
1. Public Land Survey	T <u>8N</u> R <u>15W</u>	<u>G-3</u>
	T _____ R _____	<u>NW Corner</u>
	T _____ R _____	<u>Section 10</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Dorothy Carlsson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Carl P. Englert Jr.

I, _____, in a field survey on August 27, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
G-3

L.C.R.C., Liber 2, Page 17
Fd. 3/4" Pipe
P.P., NE 78.69'
Centerline of Street Sign, SE 46.33'
Centerline Telephone Box, NW 39.70'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-3
Found 4" Harrison Mon., Broken
and accepted as a careful and
faithful perpetuation of the
position of the original corner.
Found P.P., NE 78.7'±
St. Sign, SE 46.5'±

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-3 Replaced broken Harrison Mon. with 3' long iron bar with O.C. Remon. Cap
O.C. Remon. Tag & Nail in SW side 4" Ash, S 34 degrees East 138.90'
O.C. Remon. Tag & Nail in NW side 10" Pine, S 25 degrees W 154.52'
O.C. Remon. Tag & Nail in NW side 10" Maple, S 69 degrees W 91.43'
O.C. Remon. Tag & Nail in E side 26" Ash, N 10 degrees W 146.39'
O.C. Remon. Tag & Nail in SE side P.P., N 44 degrees E 79.10'

(EDM)

Signed by Carl P. Englert Jr.
Surveyor's Michigan License No. 18987

Date December 3, 1993

