

REMONUMENTATION

OTTAWA COUNTY REMONUMENTATION

RECORDED

LAND CORNER RECORDATION CERTIFICATE

93 DEC 15 AM 9:32

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

COMMISSION

Phyllis Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

<u>Ottawa</u> (County)	Located in:	Corner Code #
	<u>Crockery Township</u>	
1. Public Land Survey	T <u>8N</u> R <u>15W</u>	<u>G-4</u>
	T _____ R _____	<u>W. 1/4 corner</u>
	T _____ R _____	<u>Section 10</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		

I, Carl P. Englert Jr. in a field survey on August 27, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-4	L.C.R.C. Liber 4, Page 243, 11/4/81
L.C.R.C. Liber 1, Page 411, 5/26/93	Fd. 1/2' Rod. Set C.I.M.
Fd. iron pipe	16" Ash S.E. 61.92'
Iron E. 33.00'	12" Ash E. 27.62'
Iron W. 33.00'	T.P. W.N.W. 29.08'
8" Pine N.E. 57.60'	P.P. S.W. 59.85'
8" Ash E. 27.55'	
8" Ash S.E. 61.46'	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-4	16" Ash S.E. 61.92'
Found 4" Broken Harrison Mon.	12" Ash E. 27.62'
and accepted as a careful and faithful perpetuation of the position of the original corner.	P.P. S.W. 59.7 ±
	Iron West 33.00'
	T.P. W.N.W. 29.10'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-4 Replace Broken Harrison with 3' long 3/4" iron bar with O.C. Remon. Cop.
 O.C. Remon. Tag & Nail in N.E. side T.P. N. 62 degrees West 29.10'
 O.C. Remon. Tag & Nail in N. side P.P. S. 64 degrees W. 59.70'
 O.C. Remon. Tag & Nail in S. side 16" Ash N.89 degrees East 28.09'
 O.C. Remon. Tag & Nail in W. side 16" Ash S. 25 degrees East 61.79'
 O.C. Remon. Tag & Nail in E. side P.P. 56 degrees West 242.96'
 (E.D.M.)

Signed by Carl P. Englert Jr.

Date December 3, 1993

Surveyor's Michigan License No. 18987

