

OTTAWA COUNTY REMONUMENTATION

RECORDED

1993

LAND CORNER RECORDATION CERTIFICATE

93 DEC 15 AM 9:32

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION

Polycarpus Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Ottawa (County) Located In: Crockery Township Corner Code #
 1. Public Land Survey T 8N R 15W G-5
 T ___ R ___ SW. corner
 T ___ R ___ Section 10
 T ___ R ___
 2. Property Controlling S ___ T ___ R ___
 in Section S ___ T ___ R ___
 3. Miscellaneous S ___ T ___ R ___
 Property in Sec. S ___ T ___ R ___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5				4	3		2				1
3													
4	7	8				9	10		11				12
5							●						
6	18	17				16	15		14				13
7													
8	19	20				21	22		23				24
9													
10	30	29				28	27		26				25
11													
12	31	32				33	34		35				36
13													

I, Carl P. Englert Jr., in a field survey on August 27, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-5 L.C.R.C. Liber 1, Page 411, 5/26/72 Fd. iron pipe T.P. E.S.E. 46.61' 24" Maple W.N.W. 92.38' 24" Maple N.N.W. 83.07' 12" Yellow Birch 86.47' S.E. Cor. Hse. N.W. 122.73'	L.C.R.C. Liber 4, Page 69, 6/5/80 Fd. 1" iron pipe, Set C.I.M. Guy P. S.E. 46.47' F.P. W.S.W. 28.28' 22" Cherry N.W. 92.36' 30" Maple N.N.W. 83.08' Cen. St. Sign N.E. 61.78'
---	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-5 Found 4" Harrison and accepted as a careful and faithful perpetuation of the position of the original corner.	Found 24" Maple N.N.W. 83 ± to face T.P. E.S.E. 46.61' S.E. Cor. Hse. N.W. 122.7 ±
--	--

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-5 4" Harrison Cast Iron Monument 8" Deep.
 O.C. Remon, Tag & Nail in E. side 28" Maple N. 12 degrees W. 84.52'
 O.C. Remon, Tag & Nail in S. side 18" Maple N. 63 degrees W. 115.74'
 O.C. Remon, Tag & Nail in N. side T.P. S. 77 degrees E. 46.75'
 O.C. Remon, Tag & Nail in W. side 20" White Pine N. 31 degrees E. 143.98'
 S.W. corner Metal Pole Barn N. 58 degrees E. 168.55'
 (EDM)

Signed by Carl P. Englert Jr.
Surveyor's Michigan License No. 18987

Date December 3, 1993

