

**SURVEY &
REMONUMENTATION**

APR 24 1995

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:52

COMMISSION

For corners in

Deborah A. Callahan
REGISTER OF DEEDS
OTTAWA COUNTY, MI

<u>Ottawa</u> (County)	Located In: Crockery Twp.	Corner Code # G-8
1. Public Land Survey	T <u>8N</u> R <u>15W</u>	<u>E 1/4 Corner</u> <u>Section 21</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Carl P. Englert, in a field survey on June 26, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
G-8 1/4 corner common to Sections 21 & 22.
Original Gov't corner set March 1837
by John Mullett

L.C.R.C. Liber 3, Page 298 (9/18/78)
Fd. 5/8" Iron, Set C.I.M.
30" Ash S.E. 46.36'
Ash Stump W.N.W. 39.79'
⊕ Tel. Cable Marker W. 37.53'
⊕ Gas Line Marker N.N.E. 85.06'

Hickory 12" 1/4 Section corner.

See back of sheet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
G-8 1/4 corner common to Sections 21 & 22.
Found Broken 4" Harrison Cast Iron Mon. 6" Deep 2'+/- W. of ⊕ Gravel Rd.
Found 30" Ash S.E. 46.36'+/- (No Nail)
Found Gas Line Marker N.N.E. 85.06'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94

Madison D. Nedwell

Accepted as a careful and faithful perpetuation of the original position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
G-8 1/4 corner common to Sections 21 & 22.
4" Harrison Cast Iron Monument with Broken Top.
O.C. Remon. Tag & Nail in W. side 36" Ash S12°E 158.72'
O.C. Remon. Tag & Nail in S.W. side 30" Ash S41°E 47.62'
O.C. Remon. Tag & Nail in N. side P.P. S89°W 63.84'
Bolt in S.E. corner G.T.E. Vault S68°W 42.48'



Signed by Carl P. Englert Jr.
Surveyor's Michigan License No. 18987

Date 12/1/94

