

SURVEY & REMONUMENTATION

APR 24 1995

OTTAWA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE

94 DEC 15 AM 11:52

Filing Requirement of Act 74, Mich. P.A. 1970

For corner **COMMISSION**

Politically Robinson Twp.

Edythe Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI.

Ottawa
(County)

Located In: Crockery Twp. Corner Code #

- 1. Public Land Survey T 8N R 15W G-13
T ___ R ___ S.E. Corner
T ___ R ___ Section 33
T ___ R ___
- 2. Property Controlling S ___ T ___ R ___
in Section S ___ T ___ R ___
- 3. Miscellaneous S ___ T ___ R ___
Property in Sec. S ___ T ___ R ___

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

I, Carl P. Englert, in a field survey on December 01, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-13 corner common to Sections 33 & 34
Original Gov't corner set May 1832
by Calvin Britain D.S.

LCRC Liber 4, Page 271 (12/3/81)
G-13

Set corner to Sections 33 & 34
Pine 20" N84°E 19 Links
Pine 24" N40°E 16 Links

Set Cast Iron Monument
12" Willow SSW 95.39'
8" Oak ENE 60.82'
14" Oak SE 67.63'
Robinson Corner E 13.40'

(See back of page)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-13 corner common to Sections 33 & 34

Found 4" Harrison CIM in Mon. Box 3" deep 3'+/- W. of Road E
Found 24" W. Oak N18°W 95.25' (No Nail)
Found 14" Oak S.E. 67.63' (No Nail)
Found Robinson Corner E. 13.40'

P.A. 345 OTTAWA COUNTY

PEER APPROVED 12/12/94
Andrey D. Nedewell

Accepted as a careful and faithful perpetuation of the original position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


G-13 corner common to Sections 33 & 34

4" Harrison Cast Iron Mon. in Mon. Box
O.C. Remon. Tag & Nail in S.W. side 18" Tw. Oak
O.C. Remon. Tag & Nail in S.E. side 8" Maple
O.C. Remon. Tag & Nail in N.E. side 30" Oak
O.C. Remon. Tag & Nail in N.W. side Power Pole
Corner to Town 7 North, Range 15 West

S60°E 67.36'
S31°W 74.48'
N22°W 95.67'
N35°E 143.17'
East 13.40'

Signed by Carl P. Englert
Surveyor's Michigan License No. 18987

Date 12/5/94



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, REVISED JAN. 1983

LCRC Liber 3, Page 174, 6/14/77

G-13 "T" Iron

E Road	E	8'
6" Silver Maple	S66°E	59.81'
36" B. Willow	S15°E	117.29'
24" W. Willow	N18°W	95.25'
NW corner Section		
T7N, R15W	E	13.40'