

LAND CORNER RECORDATION CERTIFICATE

93 DEC 15 AM 9:31

Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

Ottawa  
(County)

Located In: Corner Code #  
Crockery Township

- 1. Public Land Survey T 8N R 15W I-3  
T \_\_\_ R \_\_\_ NE Corner  
T \_\_\_ R \_\_\_ Section 10  
T \_\_\_ R \_\_\_
- 2. Property Controlling S \_\_\_ T \_\_\_ R \_\_\_  
in Section S \_\_\_ T \_\_\_ R \_\_\_
- 3. Miscellaneous S \_\_\_ T \_\_\_ R \_\_\_  
Property in Sec. S \_\_\_ T \_\_\_ R \_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

*Polina Chittman*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

Carl P. Englert Jr.

I, \_\_\_\_\_, in a field survey on August 30, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3									●				
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- I-3 L.C.R.C., liber 2, Page 17 L.C.R.C., Liber 2, Page 59, (2-16-1973)  
(2-16-1973) Fd. 1/2" rod in monument box  
Fd. iron in monument box NE 35.16', 12" Maple  
E 34.92', T.P.  
SE 76.00', 17" Maple

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- I-3 Found 3" broken Harrison Mon. NE 35.16', 14" Maple  
and accepted as a careful and E 34.92', T.P.  
faithful perpetuation of the SE 76.00', 24" Maple  
position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-3 Set O.C. Remon Cap over broken 3" Harrison Mon. in Mon. Box  
O.C. Remon. Tag & Nail in W side 26" Maple, S 8 degrees E 214.89'  
O.C. Remon. Tag & Nail in W side 24" Maple, S 23 degrees E 76.54'  
O.C. Remon. Tag & Nail in NE side T.P., S 65 degrees E 34.99'  
O.C. Remon. Tag & Nail in SE side 14" Maple, N 73 degrees E 35.35'  
O.C. Remon. Tag & Nail in S side P.P., N 60 degrees E 97.09'

(E.D.M.)

Signed by Carl P. Englert Jr.  
Surveyor's Michigan License No. 18987

Date December 3, 1993

