

93 DEC 15 AM 9:32

OTAWA COUNTY

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
	<u>Crockery Township</u>	
1. Public Land Survey	T <u>8N</u> R <u>15W</u>	<u>I-5</u>
	T _____ R _____	<u>SE Corner</u>
	T _____ R _____	<u>Section 10</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Richard R. Robinson
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Carl P. Englert Jr.

I, _____, in a field survey on August 30, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-5
 L.C.R.C., Liber 1, Page 581
 (8-7-1972)
 Fd. Mon. Box & Iron Pipe
 T.P., NE 65.63'
 8" Pine, NE 78.59'
 St. Sign, SE 57.13'
 P.P., SW 45.04'
 12" Maple, WNW 67.18'

L.C.R.C., Liber 5, Page 91
 (12-20-1983)
 FD. Bolt Spike, Set C.I.M.
 P.P., SE 45.17'
 P.P., NNW 80.09'
 T.P., NE 65.58'
 St. Sign, SE 57.05'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-5
 Found broken 4" Harrison Mon. in Mon. Box
 and accepted as a careful and faithful
 perpetuation of the position of the original
 corner.

P.P. NWW 80.89'
 St Sign SE 57.05'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-5 Set O.C. Remon. Cap over broken 4" Harrison Mon. in Mon. Box
 O.C. Remon. Tag & Nail in W side 15" Spruce, N 46 degrees E 69.34'
 O.C. Remon. Tag & Nail in NE side 26" Spruce, S 33 degrees E 80.66'
 Centerline top bolt on hydrant, N 50 degrees E 50.96'
 O.C. Remon. Tag & Nail in SW side P.P., N 27 degrees W 80.16'
 O.C. Remon. Tag & Nail in SE side 26" Maple, S 71 degrees W 117.68'

(E.D.M.)

Signed by Carl P. Englert Jr.
 Surveyor's Michigan License No. 18987

Date December 3, 1993
 REGISTERED LAND SURVEYOR
 No. 18987
 FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28 1977