

**SURVEY &
REMONUMENTATION**

APR 05 1996

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION** Crockery Twp.
Ottawa (County) Located in: Corner Code #

- | | | |
|---------------------------------------|----------------------------|------------------------|
| 1. Public Land Survey | T <u>8</u> N R <u>15</u> W | I - 8 |
| | T _____ R _____ | W $\frac{1}{4}$ Corner |
| | T _____ R _____ | Section 23 |
| | T _____ R _____ | |
| 2. Property Controlling in Section | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

RECORDED

95 NOV 15 PM 2:06

Edythe S. Holman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, Carl P. Englert, Jr., in a field survey on October 18, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- I - 8 $\frac{1}{4}$ corner common to Sections 22 & 23 LCRC Liber 2, Page 409
 Original Corner set March 1837 11/28/73
 by John Mullett, D.S. Found "T" Iron in Mon Box
 Set $\frac{1}{4}$ Section Post SW 16" Ash 37.72'
 Sugar 15" N 64° E 7 Links E 12" Tree 30.63'
 Sugar 16" S 70° W 33 Links NW 17" Ash 72.05'
 NE 8" Ash 55.55'

see other side

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- I - 8 $\frac{1}{4}$ corner common to Section 22 & 23
 Found "T" Iron in Mon Box on CL 112th Avenue, Set 2' Long X 3/4" Steel Bar
 with Ottawa County Remonumentation Cap. P.A. 345 OTTAWA COUNTY
 Found 12" Ash E. 30.63
 Found 8" Ash NE 55.55'
 Found 30" Ash W. 64.50' (stump)
 Found 24" Hickory SW 95.50'

PEER APPROVED 10/23/95


William D. Newell
W.D.N.

Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I - 8 $\frac{1}{4}$ corner common to Sections 22 & 23
 2' Long X 3/4" Steel Bar with Ottawa County Remonumentation Cap in Monument Box
 Ottawa County Remonumentation Tag and Nail in SW side of P.P. S 50° E 47.51'
 Ottawa County Remonumentation Tag and Nail in SE side of 12" Ash N 33° E 55.59'
 Ottawa County Remonumentation Tag and Nail in SW side of 7" Oak N 28° W 74.54'
 Ottawa County Remonumentation Tag and Nail in NW side 24" Hickory S 32° W 95.31'

Signed by Carl P. Englert Jr
 Surveyor's Michigan License No. 18987



October 21, 1995

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

I - 8. T 8 N, R 15 W Crockery Township
LCRC Liber 3, Page 149 October 12, 1976
16" Ash SW 37.22'
12" Ash E. 30.63'
17" Ash NW 72.05'
8" Ash NE 55.55'
12" Maple NW 38.70'
30" Ash W. 64.50'
24" Hickory SW 95.50'

\$ 11.00 CORNER