

**SURVEY &
REMONUMENTATION**

APR 24 1995

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**

94 DEC 15 AM 11:49

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

D. J. ...
REGISTER OF DEEDS
OTTAWA COUNTY, MI

<u>Ottawa</u> (County)	Located In: Crockery Twp.	Corner Code # <u>I-11</u>
1. Public Land Survey	T <u>8N</u> R <u>15W</u>	<u>NE Corner</u> <u>Section 34</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Carl P. Englert, in a field survey on December 07, 19 94
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

I-11 corner common to Sections 26, 27, 34 & 35
Original Gov't corner set March, 1837
by John Mullet D.S.

Set Post
Beech 16" N66°E 7 Links
Maple 13" S53°W 55 Links

LCRC Liber 5, Page 172 (12/14/84)
Set CIM
32" Oak NNW 9.49'
17" Oak W 19.97'
10" Pine SE 35.27'
20" Oak E 40.45'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-11 corner common to Sections 26, 27, 34 & 35

Found 4" Harrison CIM at Ground Level
Found 32" Oak NNW 9.49'
Found 17" Oak W 19.97'
Found 10" Pine SE 35.27'
Found 20" Oak E 40.45'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94
Reddy D. McDowell

Accepted as a careful and faithful perpetuation of the
original position of the corner.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-11 corner common to Sections 26, 27, 34 & 35

4" Harrison Cast Iron Monument
O.C. Remon. Tag & Nail in W. side 22" Oak N 5°E 38.62'
O.C. Remon. Tag & Nail in N. side 24" Oak N80°E 40.34'
O.C. Remon. Tag & Nail in N.E. side 36" Oak N45°W 9.44'
O.C. Remon. Tag & Nail in S. side 17" Oak S85°W 19.98'

Signed by Carl P. Englert Jr.
Surveyor's Michigan License No. 18987

Date 12/11/94



FORM APPROVED BY MICHIGAN STATE BOARD OF SURVEYORS
REVISED JAN., 1993