

SURVEY & REMONUMENTATION

RECORDED

JUN 28 1999

98 NOV 11 PM 1:26

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

Greg Schiltz
**REGISTER OF DEEDS
OTTAWA COUNTY, MI**

For corners in **SECTION**

Robinson Twp.

Ottawa
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--------------------------|-------------------|
| 1. Public Land Survey | T <u>8N</u> R <u>15W</u> | <u>I-13</u> |
| | T ___ R ___ | <u>SW CORNER</u> |
| | T ___ R ___ | <u>Section 35</u> |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Carl P. Englert, Jr., in a field survey on Oct. 16 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

| | | | | | | | | | | | | | |
|----|---|----|----|----|----|----|----|---|---|---|---|---|---|
| 1 | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-13 Corner common to Section 34 & 35, T8N, R15W

G.L.O. 1832 by Calvin Britain
Set corner to Sec. 34 & 35
Pine 40" N 31° E 31 Links
Pine 30" N 43° W 57 Links

E.H. Peck County Surveyor 1906
Found Stake
Pine 40" N 31° E 20.5'
This corner shown on Survey Notes
by Exxel Eng. Oct., ~~1988~~ 1988

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-13 Found 4" Cast Iron Monument

Found NW corner Section 2, T7N, R15W East 39.80'

10/19/98
[Signature]

Accepted as a careful and faithful perpetuation of the original position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13 Corner common to Sections 34 and 35, T8N, R15W

4" Harrison Cast Iron Monument

- O.C. Remon Tag & Nail in SE side 4" Oak N 40° E 92.35'
- O.C. Remon Tag & Nail in NE side 5" Oak N 53° W 73.86'
- O.C. Remon Tag & Nail in SE side 7" Oak S 50° W 61.44'
- O.C. Remon Tag & Nail in SW side 8" Cherry S 31° E 53.96'
- NW corner Section 2, T7N, R15W East 39.80'



Receipt #19293

Signed by Carl P. Englert Jr.
Surveyor's Michigan License No. 18987

Date 10/17/1998

\$1.00 PHOTO
Receipt #19293