

**SURVEY &
REMONUMENTATION**

APR 25 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC -8 PM 12:37

Richard L. Williams
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
	Crockery Twp	
1. Public Land Survey	T <u>8N</u> R <u>15W</u>	<u>J-5</u>
	T _____ R _____	<u>S1/4 Corner</u>
	T _____ R _____	<u>Section 11</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5					▲							
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Carl P. Englert in a field survey on March 16, 1994,
to hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
J-5 1/4 corner common to Section 11 and 14.

Original gov't corner set March 1837
by John Mullet
Set Post
Beech 6" S72°E 10 Links
Do 9" N37°W 30 Links

LCRC Liber 2, Page 73 (3/23/73)
Fd. Cast Iron Monument
P.P. NNW 24.62'
10" Pine NNE 57.67'
16" Cherry SE 34.95'
Tel. Pole WSW 84.56'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
J-5 1/4 corner common to Sections 11 and 14.

Found 4" Cast Iron Monument with top broken off in mon. box
Found Nail in P.P. NNW 24.62'

Accepted as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 OTTAWA COUNTY
PEER APPROVED 11/21/94

Madison P. Hudson

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-5 1/4 corner common to Sections 11 and 14.
4" Harrison C.I.M. with broken top in Monument Box
O.C. Remon. Tag & Nail in NW side 40" Maple S44°W 81.32'
O.C. Remon. Tag & Nail in W side P.P. N17°W 25.01'
O.C. Remon. Tag & Nail in N side 20" Ash S76°E 115.65'
O.C. Remon. Tag & Nail in SW side 22" Maple S40°E 53.88'
Centerline Top Bolt on fire hydrant North 44 degrees East 45.14'
Centerline pavement 3' +/- North



Signed by Carl P. Englert Date 11/17/94
Surveyor's Michigan License No. 18987