

**SURVEY & REMONUMENTATION**

JUN 28 1999

**OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**RECORDED**

98 NOV -4 PM 2: 31

**SECTION**

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>15W</u>	J-13 S 1/4 sec. 35 <u>CROCKERY TWP</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*Ray [Signature]*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, ROBERT LEMKE, in a field survey on OCT. 16, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(see back of page)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found iron pipe 1" od  
Witness's per county survey notes 1968  
8" Pine NW R=39.99 (M=40.50' to nail in South face) now 10" Pine  
24" Oak WNW R= 38.92 (M=38.75' to nail in East face) now 30"  
NE Corn. Hse. Proper SW R=47.28 (M=46.75')  
8" Cherry ESE 44.57 (not found)

Witness's per Act 132 survey Liber 4, Page 454  
N 1/4 corner Sec. 2, T7N, R15W East R=19.80' (M=19.80')

And is accepted as a careful and faithful perpetuation of the position of the original corner.

APPROVED BY 10/19/98  
*[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 36" iron rod w/ Ottawa County Remon Cap  
O.C. Remon nail & tag in the NE side of a 10" Pine N 30°W 40.80'  
Found O.C. Remon nail & tag in the N side of a 30" Oak N 75°W 39.63'  
Found O.C. Remon nail & tag in the E side of a Power Pole S 30°W 90.70'  
Broken Cast iron monument 1.0' below grade of gravel road which is the N1/4 cor. Sec 2, T7N, R15W East 19.80'  
(as shown by Act 132 survey Liber 4, Page 454)



APPROVED REMONUMENTATION  
P.A. 345 OF 1990  
OTTAWA COUNTY  
DATE APPROVED \_\_\_\_\_  
COUNTY REP. \_\_\_\_\_

Signed by Robert E. Lemke  
Surveyor's Michigan License No. 40160

Date 10/16/98

SURVEY &  
REMONUMENTATION

JUN 28 1999

SECTION

Description of original monument and accessories and / or subsequent restoration: J-13 continued

GLO 1837 J.A. Gillett  
West on South side of Sec. 35  
40.0 Ch.  
Set 1/2 mile post  
Pine 40 N 44° E 47 lks  
Pine 25 N 58° W 31 lks

County Survey notes  
Section 35, T8N, R15W  
Stone: See Sec.2-7-15. 4/18/06. 4/15/09

County Survey notes 1968  
Section 35 T8N, R15W  
Found iron  
iron is 21' +/- West of cl road  
8" Pine NW 39.99  
24" Oak WNW 38.92  
NE Corn. Hse. Proper SW 47.28  
8" Cherry ESE 44.57

Act 132 survey Liber 4, Page 454  
Exxel Engineering Inc.  
October 15, 1979  
N ¼ cor. Sec 2, T7N, R15W  
Cast Iron Mon.  
30" Oak WNW 59.55'  
Iron E 33.02'  
NE cor. Hse #14407 SW 64.32'  
S ¼ cor. Sec. 33-8-15 W. 19.80'