

# SURVEY & REMONUMENTATION

APR 24 1995

OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:49

For corners in **COMMISSION**

*Phyllis Caldwell*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Ottawa <small>(County)</small>	Located in: Crockery Twp.	Corner Code # K-4
1. Public Land Survey	T <u>8N</u> R <u>15W</u>	<u>K-4</u>
	T _____ R _____	<u>E 1/4 Corner</u>
	T _____ R _____	<u>Section 11</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11	▲	12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Carl P. Englert, in a field survey on December 07, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

K-4 1/4 corner common to Sections 11 & 12  
Original Gov't corner set March, 1837  
by John Mullet D.S.

Set 1/4 Section Post  
Beech 15" N22°W 13 Links  
Hemlock 10" S38°E 26 Links

LCRC Liber 2, Page 77 (3/14/73)  
Found Post & Stake  
Set Angle Iron  
36" Beech SE 44.95'  
18" Cherry SE 33.66'  
8" Oak SW 13.29'  
36" Maple N 71.45'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-4 1/4 corner common to Sections 11 & 12

Found 4" Harrison CIM 2½' deep  
Found 36" Beech S.E. 44.95'  
Found 18" Cherry S.E. 33.44'

PA. 345 OTTAWA COUNTY  
PEER APPROVED 12/12/94

*Wesley D. Nelson*

Accepted as a careful and faithful perpetuation of the original position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-4 1/4 corner common to Sections 11 & 12

Set 3/4" x 2' long steel bar with O.C. Remon. Cap over 4" Cast Iron Mon.  
O.C. Remon. Tag & Nail in W. side 36" Beech S38°E 46.10'  
O.C. Remon. Tag & Nail in W. side 24" Cherry S58°E 33.66'  
O.C. Remon. Tag & Nail in S. side 6" Maple EAST 12.60'  
O.C. Remon. Tag & Nail in E. side 10" Ash N20°E 19.75'

Signed by Carl P. Englert  
Surveyor's Michigan License No. 10907

Date 12/11/94

