

**SURVEY & REMONUMENTATION**

**DEC 01 1998**

**SECTION**

**OTTAWA COUNTY REMONUMENTATION  
OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

**RECORDED**

**98 JUL 24 PM 1:45**

For corners in

Ottawa \_\_\_\_\_  
(County)

Located In:

Corner Code #

- 1. Public Land Survey T8N \_\_\_ R15W\_ K-6  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_  
West 1/4 corner  
Section 13
- 2. Property Controlling S \_\_\_ T \_\_\_ R \_\_\_  
in Section S \_\_\_ T \_\_\_ R \_\_\_
- 3. Miscellaneous S \_\_\_ T \_\_\_ R \_\_\_  
Property in Sec. S \_\_\_ T \_\_\_ R \_\_\_  
Crockery Twp.

*Long Schultz*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

**Register of Deeds Stamp & File Number**

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Steve Lampen \_\_\_\_\_, in a field survey on July 16, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5			4			3		2			1
3													
4	7	8			9			10		11			12
5													
6	18	17			16			15		14			13
7													
8	19	20			21			22		23			24
9													
10	30	29			28			27		26			25
11													
12	31	32			33			34		35			36
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- K-6 Peck - Stake, original witness good
- GLO - Mullett - 1837 B. Cherry 4 N 41 E 26 lks
- North between Section 13 & 14 Beech 8 N 32 W 57 lks
- 40.00 set 1/4 section post K-6 to K-7 = 2652 ft.
- Hemlock 12 N 27 E 19 K-6 to I-6 = 5396 ft.
- Beech 6 S 23 W 16

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-6 Could not find the stake or witnesses by Peck.

Re-established the corner on an old North and South fence 2652 ft North of K-7. This position fits the old East and West fence along the East and West 1/4 line near the NE corner of the NW 1/4 of the SE 1/4, Section 14. Measure K-6 to I-6 = 5390 ft.

Set an Ottawa County Remonumentation iron and cap and is accepted as a careful and faithful re-establishment of the position of the corner.

SEE SKETCH ON BACK.

PA. 345 OTTAWA COUNTY  
PEER APPROVED 6-15-98  
*A.D.N.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-6 Ottawa County Remonumentation iron and cap.

- Remonumentation tag in West side 20" Beech 213°40' 4.02 ft.
- Remonumentation tag in NW 14" Cherry 231° 44' 16.25 ft.
- Remonumentation tag in South 16" Maple 289° 42' 34.03 ft.
- Remonumentation tag in West 20" Maple 167° 32' 27.58 ft.

\$11.00 CORNER Receipt #5013

Signed by Steven Lampen Date JULY 20, 1998  
Surveyor's Michigan License No. 37279

SURVEY &  
REMONUMENTATION

DEC 01 1998

SECTION

