

FEB 18 1994

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

93 NOV -8 PM 1:52

For corners in COMMISSION

*Robert C. ...*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

<u>Ottawa</u> (County)	Located In:	Corner Code #
	Crockery Twp.	W. 1/4 Cor. Sec 24
1. Public Land Survey	T <u>8N</u> R <u>15W</u>	<u>K-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Carl P. Englert Jr.

in a field survey on August 2, 19 93  
I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

1. Description of original monument and accessories and/or subsequent restoration:

K-8	L.C.R.C. Liber 4 Page 105	L.C.R.C. Liber 6 Page 243
Fd. 5/8" Iron Bar, Set C.I.M.		Fd. C.I.M. in center of intersection
Tel. Pedestal SW 61.40		S 42 E 41.61 Nail in corner fence post
Fence Post SE 41.51		S 16 E 89.81 Nail in W. side 8" Oak
Center Street Sign N 25.81		S 66 W 61.08 NE Cor. Tel. Riser Box
Tel. Cable Sign ESE 83.23		N 13 E 23.85 Face of E. Leg Sign Post

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-8  
Fd. 4" Harrison Monument  
SE 41.5± Corner Fence Post  
SW 61.4 Tel. Pedestal  
N 25.8± Center St. Sign

3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8  
4" Cast Iron Harrison Monument, Good Condition, 4"± deep  
O.C. Remon. Tag & Nail in N. side 8" Ash S 75 E 107.49  
O.C. Remon. Tag & Nail in W. side P.P. N 40 E 164.92  
O.C. Remon. Tag & Nail in W. side 8" Ash S 19 E 89.59  
O.C. Remon. Tag & Nail in E. side P.P. S 55 W 307.43  
O.C. Remon. Tag & Nail in S. side 6" Elm N65 W 62.42  
Center of intersection of gravel roads  
(EDM)

Signed by Carl P. Englert Jr.  
Surveyor's Michigan License No. 18987

Date Oct. 6, 1993

