

SURVEY & REMONUMENTATION

FEB 18 1994

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

93 NOV -8 PM 1:52

Edythe Chubb
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

Ottawa
(County)

Located In: Corner Code #

Crockery Township

- | | | |
|------------------------------------|--------------------------|---|
| 1. Public Land Survey | T <u>8N</u> R <u>15W</u> | K-10, West $\frac{1}{4}$ corner, Section 25 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Carl P. Englert Jr.

August 3, 19 93

I, _____, in a field survey on _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | | | |
|------|--|-----------------------------|---|
| K-10 | L.C.R.C., Liber 5, Page 148 | L.C.R.C., Liber 4, Page 105 | L.C.R.C., Liber 1, Page 259 |
| | Cast iron monument | Fd. 5/8" iron bar | Set 5/8" bar 25' East of down F.P. on fence lines East and West |
| | P.P., Northeast 51.05' | F.P., East 30.00' | West 25' to fence line P.P., Northeast 51.10' |
| | F.P., East 30.70' | F.P., Northeast 51.10' | |
| | Centerline Leonard Road, South 734.19' | | |
| | July, 1983 | | |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- K-10
Fd. C.I.M.
Fence Post, East 30.7'
Fence line East, 3' West of centerline of gravel road
P.P., Northeast 51.05'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-10
Fd. 4" Harrison Cast iron monument
O.C. Remon. Tag and Nail in W. side P.P., S. 5 degrees E., 329.56'
O.C. Remon. Tag and Nail in W. side Guy P., N. 5 degrees W., 420.80'
O.C. Remon. Tag and Nail in W. side P.P., N. 34 degrees E., 51.04'
O.C. Remon. Tag and Nail in S. side fence post, E. 31.23'

(E.D.M.)

Signed by *Carl P. Englert Jr.*
Surveyor's Michigan License No. 18987

Date Oct 6, 1993

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 2 1975

