

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

For corners in

OTTAWA COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

93 NOV -8 PM 1:52

Phyllis C. ...
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Ottawa (County)	Located In:	Corner Code #
	Crockery Twp. SW Cor. Sec. 25	
1. Public Land Survey	T <u>8N</u> R <u>15W</u>	<u>K-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Carl P. Englert Jr.

I, _____, in a field survey on July 29, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-11	L.C.R.C. Liber 4 Page 103	L.C.R.C. Liber 1, Page 529
Fd. 5/8" Bar, Set. C.I.M.	Fd. Bent "T" Iron, Set 5/8" Bar	
Tel. Pedestal S.W. 47.53	NNW 14" Walnut 133.1	
13" Sycamore N.E. 56.50	NE 14" Sycamore 56.50	
Cen. St. Sign E. 31.81	SW 6" Ash 47.80	
10" Cherry S.E. 44.84	E. St. Sign 31.85	

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-11
Fd. 4" Harrison Mon. (Broken) 2'± South of Centerline of Garfield on 104th Ave
16" Sycamore NE 56.47
St. Sign E 32'±

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-11	Set 3' long 3/4" Iron bar with O.C. Remonumentation Cap	
O.C. Remon. Tag & Nail in W. side of 16" Sycamore	N 35 E 56.47	
O.C. Remon. Tag & Nail in SW. side P.P.	S 64 E 99.96	
O.C. Remon. Tag & Nail in SW. side 10" Maple	S 25 E 93.76	
O.C. Remon. Tag & Nail in E. side 10" Aspen	S 15 W 101.88	
O.C. Remon. Tag & Nail in SE. side P.P.	S 73 W 201.19	

(EDM)

Signed by Carl P. Englert Jr.
Surveyor's Michigan License No. 18987

Date Oct. 6, 1993

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 2, 1988

