

FEB 24 2000

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
99 SEP 23 PM 3: 21

Doug Schiller
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in SECTION

<u>Ottawa</u> (County)	Located In: Crockery Township	Corner Code # K-12
1. Public Land Survey	T 8N R 15W	E 1/4 corner Section 35
	T ___ R ___	
	T ___ R ___	
	T ___ R ___	
2. Property Controlling in Section	S ___ T ___ R ___	W 1/4 Corner Section 36
	S ___ T ___ R ___	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	
	S ___ T ___ R ___	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Carl P. Englert, in a field survey on May 27, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-12 1/4 Corner Common to Sections 35 and 36
 G.L.O. John Mullett 1837 LCRC Liber 1, Page 615
 Set 1/4 Section Post Englert 1972
 Beech 8 inch S82°W 27 Links Found Large "T" Iron
 Beech 9 inch S77°E 10 Links 20" Pine East 23.75'
 20" Maple North 37.80'
 30" Pine NW 63.03'

See Other Side

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-12 Found 4" Harrison Cast Iron Monument in centerline of Gravel Road
 0.5' below grade
 Found Triple Maple South 95.5'
 Found 16" Pine East 37.80'

Accepted as a careful and faithful perpetuation of the original position of the corner.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-12 4" Harrison Cast Iron Monument
 O.C. Remon Nail and Tag in SW side 18" Maple N24°W 88.60'
 O.C. Remon Nail and Tag in W Side 12" Maple N34°E 70.87'
 O.C. Remon Nail and Tag in S Side 26" W. Pine N79°E 37.67'
 O.C. Remon Nail and Tag in E Side 30" Maple S 2°W 95.69'
 Found 1/2" capped Iron East 32.97"

9/13/99

Signed by Carl P. Englert
Surveyor's Michigan License No. 18987

Date 9/13/1999



FEB 24 2000

SECTION

K-12 T8N, R15W Joiner 1980
Found 1/2" Iron Bar, Set Cast Iron Monument inscribed
"Section Corner"
30" Pine NW 63.42'
16" Pine E 37.80'
18" Triple Maple S 95.48'