

**SURVEY &
REMONUMENTATION**

OCT 07 1996

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Ottawa</u> (County)	Located In: Crockery Twp.	Corner Code #
1. Public Land Survey	T 8N R 15W	L-3
	T R	N 1/4 corner
	T R	Section 12
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Carl P. Englert, Jr., in a field survey on 11/16, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-3 1/4 corner common to Sections 1 & 12	LCRC Liber 2, Page 263, 8/4/1973
Original government corner set March 1837	Found angle iron and wood stake
by John Mullett	SE 47.25' 15" Locust
Set 1/4 section post	S 24.02' 9" Locust
Beech 12" N 71° W 7 links	SW 31.68' 11" Locust
Sugar Maple 14" S 87° E 23 links	

SEE OTHER SIDE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-3 1/4 corner common to Sections 1 & 12
Found cast iron monument 8" below grade in centerline of gravel road
Found 15" Locust SE 47.25'

P.A. 345 OTTAWA COUNTY

PEER APPROVED 8-20-96

Carl P. Englert Jr.

Accepted as a careful and faithful perpetuation of the original position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-3 1/4 corner common to Section 1 & 12
4" cast iron monument in centerline of gravel road 8" below grade
Ottawa County Remonumentation tag and nail in W side P.P. N 32° W 239.35'
Ottawa County Remonumentation tag and nail in SW side 12" Lucust S 50° W 57.34'
Ottawa County Remonumentation tag and nail in E side 15" Lucust S 05° E 40.05'
Ottawa County Remonumentation tag and nail in W side 12" Lucust S 25° W 49.24'

Signed by Carl P. Englert Jr.
Surveyor's Michigan License No. 18987

Date 11/20/1995



RECORDED
96 AUG 26 PM 2:02

D. J. ...
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

L-3 Town 8 North, Range 15 West
LCRC Liber 4, Page 94, 7/15/1980
Found angle iron and stone, set cast iron monument
15" Lucust SE 47.16'
9" Lucust S 24.15'
11" Lucust SW 31.67'
6" Lucust NE 72.56'

SURVEY &
REMONUMENTATION

OCT 07 1996

COMMISSION

\$ 11.00 CORNER
\$ 1.00 PHOTO
\$ 1.00 PHOTO