

SURVEY & REMONUMENTATION

OCT 07 1996

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

OTTAWA Located in: Crockery Twp. Corner Code # _____
(County)

1. Public Land Survey T 8N R 15W L-5
T _____ R _____ S 1/4 corner
T _____ R _____ Section 12
T _____ R _____
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

RECORDED

96 AUG 26 PM 2:02

Richard R. Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Carl P. Englert, Jr., in a field survey on November 16 19 95 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-5 1/4 corner common to Sections 12 & 13
Original Government corner set March 1837
by John Mullett
Set 1/4 Section Post
Hemlock 6" S 78° W 6 links
Hemlock 12" N 40° E 12 links

LCRC Liber 3, Page 137, 9/17/1976
Found Axle
ENE P.P. 9.31'
NNE 17.12' 12" Ash
W 10.95' 10" Maple
SW 27.27' Twin Cherry

P.A. 345 OTTAWA COUNTY

SEE OTHER SIDE

PEER APPROVED 8-20-96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-5 1/4 corner common to Sections 12 & 13
Found 4" cast iron monument with top broken off in fence corner
Found P.P. ENE 9.31'
Found 12" Ash NNE 17.20'
Found Twin Cherry SW 27.15'

Richard R. Robinson

Accepted as a careful and faithful perpetuation of the original position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-5 1/4 corner common to Sections 12 & 13
4" cast iron monument with top broken off 6" below grade
Ottawa County Remonumentation tag and nail in E side 12" Ash N 20° E 16.85'
Ottawa County Remonumentation tag and nail in E side 12" Ash N 33° W 36.06'
Ottawa County Remonumentation tag and nail in S side 14" Maple S 60° W 24.05'
Ottawa County Remonumentation tag and nail in E side 10" Maple S 11° W 12.61'
Ottawa County Remonumentation tag and nail in S side P.P. N 75° E 9.22'

Signed by Carl P. Englert Jr.
Surveyor's Michigan License No. 18987

Date 11/20/1995



L-5 Town 8 North, Range 15 West
LCRC Liber 4, Page 241, 10/30/1981
Found Axle, Set cast iron monument
P.P. ENE 9.39'
Twin Cherry SW 27.15'
Fence Post South 1.50'
12" Ash NNE 17.20'

SURVEY &
REMONUMENTATION

OCT 07 1996

COMMISSION

\$ 11.00 CORNER
\$ 1.00 PHOTO
\$ 1.00 PHOTO