

SURVEY & REMONUMENTATION

FEB 18 1994

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

93 NOV -8 PH 1:52

Richard R. Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

or corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
	Crockery Township	
Public Land Survey	T <u>8N</u> R <u>15W</u>	<u>L-7, N 1/4 cor-</u> <u>ner, Sec. 24</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

Carl P. Englert Jr.

in a field survey on July 20, 19 93

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

L-7
Liber 4, Page 270, December, 1981
Fd. iron pipe, Set C.I.M.
P.P. N. 56.65'
2" Steel Post NE 60.59'
Center of Old U.S. 16, South 28.15'
West edge gravel Drive East 34.00'

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-7
Fd. 4" Harrison Monument
P.P. North 56.68'
South, centerline old US-16, 28.15'
East, 34'± West edge gravel drive

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-7
4" Cast iron Harrison Monument, Good condition, 4" deep
Ottawa County Remonumentation tag and nail in West side P.P., North 56.68'
Ottawa County Remonumentation tag and nail in South side 16" Hickory, North 84 degrees East, 309.77'
Ottawa County Remonumentation tag and nail in SW side P.P., South 64 degrees East 378.43'
Ottawa County Remonumentation tag and nail in South side P.P. North 80 degrees West 353.71 feet
Centerline of Cleveland Street, South 28.15'
On occupation line to the North (EDM)

Signed by Carl P. Englert Jr. Date Oct. 6, 1993
Surveyor's Michigan License No. 18987

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

