

FEB 18 1994

OTTAWA COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

93 NOV -8 PM 1:52

*Phyllis R. Ballman*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code ==
	Crockery Twp.	
1. Public Land Survey	T <u>8N</u> R <u>15W</u>	<u>N 1/4 corner</u>
	T _____ R _____	<u>Section 25,</u>
	T _____ R _____	<u>L-9</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Carl P. Englert Jr.

I, \_\_\_\_\_, in a field survey on September 23, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-9  
L.C.R.C. Liber 5, Page 355  
Set C.I.M. at intersection of fence lines  
Twin Basswood NNW 18.28'  
15" Maple, NW 53.62'  
18" Maple, ENE 19.51'  
4" Beech, SW 19.24'

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-9  
Fd. 4" harrison Monument at fence line intersection  
West, North and South  
Twin Basswood, WNW 18'± (no nail)  
18" Maple, ENE 19.51'  
4" Beech, SW 19.24'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-9  
4" cast Iron Harrison Monument, Good condition in the bottom of ditch  
O.C. Remon., Tag & Nail in South Side Twin Basswood N 75 degrees W, 18.08'  
O.C. Remon., Tag & Nail in South side 18" Maple, N 80 degrees E, 19.50'  
O.C. Remon., Tag & Nail in NE side 16" Maple, N 40 degrees W, 40.20'  
O.C. Remon., Tag & Nail in NW Side 5" Beech, S 45 degrees W, 19.24'

(Tape)

Signed by Carl P. Englert Jr.  
Surveyor's Michigan License No. 18987

Date October 6, 1993

FORM APPROVED BY MICHIGAN STATE BOARD OF SURVEYORS

