

SURVEY &
REMONUMENTATION

OTTAWA COUNTY REMONUMENTATION

FEB 18 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

93 NOV -8 PM 1:52

Phyllis Anderson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in COMMERCIAL

Ottawa
(County)

Located In: Corner Code #

Crockery Township

- | | | |
|------------------------------------|--------------------------|--|
| 1. Public Land Survey | T <u>8N</u> R <u>15W</u> | <u>L-11, S$\frac{1}{2}$ corner, Sec. 25</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Carl P. Englert Jr.

I, Carl P. Englert Jr., in a field survey on August 2, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-11
L.C.R.C. Liber 2, Page 75, March 1973
Fd. Stone bricks & cast iron, Set C.I.M.
36" Maple, West 24.28'
18" Ash, North 92.36'
P.P., Northeast 97.19'
Southeast corner house, Southwest 126.2'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-11
Fd. broken Harrison Monument and bricks
P.P., Northeast 97.25'
40" Oak, West 25.52'
Southeast corner house, Southwest 126.2'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-11
Set 3' long iron bar with O.C. Remonumentation Cap
O.C. Remonumentation tag and nail in SE side P.P., North 40 degrees East, 97.25'
O.C. Remonumentation tag and nail in E side 15" Locust, North 18.98'
O.C. Remonumentation tag and nail in N side 40" Oak, West 25.52'
O.C. Remonumentation tag and nail in NW side 14" Maple, South 25 degrees West 23.40'
East 16'±, centerline gravel drive

(EDM)

Signed by Carl P. Englert Jr.
Surveyor's Michigan License No. 18987

Date Oct 6, 1993

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JANUARY 1975, REVISED JANUARY 1983

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

