

RECORDED

96 DEC 18 PM 4:54

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Phyllis R. Bullman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in
Ottawa
(County)

Located In: Crockery Twp.
Corner Code #

- 1. Public Land Survey T 8N R 15W L-13
T R S 1/2 corner
T R Section 36
T R _____
T R _____
- 2. Property Controlling in Section S T R _____
S T R _____
S T R _____
- 3. Miscellaneous Property in Sec. S T R _____
S T R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 16 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

Carl P. Engle in a field survey on Oct. 12 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- L-13 South 1/4 Cor. Sec. 36
- G.L.O. John Mullett 1837
- Set 1/4 Section Post
- Elm 8" N23°E 30 links
- B. Ash 7" N48°W 67 links

L.C.R.C. Liber 2, Page 75 3/23/1973
Found 3/4" Iron Pipe
N. Bank Grand River S.30'±
16" Tw. Ash W.N.W. 54.22'
24" Maple N.W. 106.92'
16" Trip. Maple N.N.E. 41.70'
24" Ash S.E. 23.10'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- L-13 South 1/4 Corner Sect. 36
- Found 3/4" pipe (Bent) in N & S fence line
- Found Ash Stump S.E. 23.1'±
- Found Trip. Maple (Dead) N.N.E. 42'±
- Grand River South 26'±

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12-9-96
C.P.E.

Accepted as a careful and faithful perpetuation of the original position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-13 South 1/4 Corner Sec. 36
- Replaced 3/4" pipe with 3/4"x3' steel bar with O.C. Remon Cap
- O.C. Remon Tag & Nail in West Side 13" Maple S5°E 21.19'
- O.C. Remon Tag & Nail in East Side 8" Ash N5°E 41.47'
- O.C. Remon Tag & Nail in North Side 10" Maple S60°E 31.80'
- O.C. Remon Tag & Nail in North Side 8" Ash N85°W 66.56'
- North Bank Grand River South 26'±

Signed by Carl P. Engle
Surveyor's Michigan License No. 13907

Date 12/11/1996

