

FEB 24 2000

RECORDED

SECTION

OTTAWA COUNTY REMONUMENTATION 99 SEP 23 PM 3: 21
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Darryl Subilletta
REGISTER OF DEEDS
OTTAWA COUNTY MI

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
	Crockery Township	
1. Public Land Survey	T <u>8N</u> R <u>15W</u>	<u>M-1</u>
	T <u> </u> R <u> </u>	<u>NE corner</u>
	T <u> </u> R <u> </u>	<u>Section 1</u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Carl P. Englert, in a field survey on 5/28, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-1 Corner common to Towns 8 and 9N, Ranges 14 and ~~13~~W.
 John Mullett D.S. 1837 LCRC Liber 2, Page 253, Englert 8/1973
 Post Found Iron Stake
 Hemlock 22" S57°W 34 Links W 33.0' Cherry
 Hemlock 18" N 8°W 28 Links SE 82.31' 8" Cherry
 LCRC Liber 2, Page 423, Englert 11/1973
 Found 3/4" Pipe
 Ties same as Liber 2, Page 253

See Other Side

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-1 Found 4" Harrison Cast Iron Monument 0.3' Below Grade in Center of Gravel Road East
 5'± West of Gravel Road North and South, Fence line West,
 0.3' Below Grade
 Found triple Cherry S60°W 28'± (No Nail)
 Record dimension checks North, ~~South~~ and East.

Accepted as a careful and faithful perpetuation of the original position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


M-1 4" Harrison Cast Iron Monument

O.C. Remon Nail and Tag in NW Side Power Pole	N61°E 190.19'
O.C. Remon Nail and Tag in NE Side Power Pole	S45°E 259.06'
O.C. Remon Nail and Tag in S Side 15" Cherry	N82°W 32.98'
O.C. Remon Nail and Tag in SE Side Triple 15" Cherry	S60°W 30.28'
O.C. Remon Nail and Tag in E Side 14" Black Locust	N24°W 77.62'

9/13/99
[Signature]

Signed by Carl P. Englert
Surveyor's Michigan License No. 18987

Date 8/30/1999



FEB 24 2000

SECTION

M-1 T8N, R15W

LCRC Liber 4, Page 97, Joiner August, 1980

Found Iron Stake, Set Cast Iron Monument, inscribed Section Corner

Triple 13" Cherry SW 27.88'

14" Cherry WNW 32.57'

Street Sign SE 44.64'

LCRC Muskegon County, Liber 1242, Page 316

SW Corner Section 31, T9N, R14W

Found Cast Iron Monument

S64°W 27.87' 14" Triple Cherry

West 33.16' 16" Cherry

LCRC Liber 1810, Page 556, Muskegon County Remon. Records,

Recorded as M-13, T9N, R15W, December 1994

Found 4" Cast Iron Monument

Ties do not fit corner.

