

**SURVEY &
REMONUMENTATION**

APR 05 1996

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **COMMISSION**
Ottawa
(County)

Crockery Twp
Located In:

Corner Code #

- | | | |
|---------------------------------------|----------------------------|-------------------|
| 1. Public Land Survey | T <u>8</u> N R <u>15</u> W | <u>M - 3</u> |
| | T _____ R _____ | <u>NE Corner</u> |
| | T _____ R _____ | <u>Section 12</u> |
| | T _____ R _____ | _____ |
| 2. Property Controlling
in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

RECORDED

95 NOV 15 PM 2:05

Deborah S. Holloman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Carl P. Englert, Jr., in a field survey on October 9, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M - 3 Corner common to Sections 1 & 12, T 8 N, R 15 W and Sections 6 & 7, T 8 N, R 14 W.
Original corner set March 1837 (LCRC Liber 2, Page 253 8/3/1973)
by John Mullett D.S. same(
Set Corner of Sections 1 & 12 (LCRC Liber 2, Page 423 11/29/1973)
Hemlock 18" S 32° W 55 Links Set 5/8" Rod from Ties
Hemlock 24" N 26° W 34 Links SW 43.3' St. Sign
SE 39.5' F. Post
NE 53.15' 18" Spruce

see other side

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M - 3 Corner common to Sections 1 & 12, T 8 N, R 15 W and Sections 6 & 7, T 8 N, R 14 W.
Found 4" CIM in center of Intersection of Gravel Roads 4" deep
Found Fencepost SE 41.98'± (Post is Leaning)
Found St. Sign SW 43.4'± (Leaning)
Found 26" Spruce NE 53.30'
Found Telephone Pedestal NW 40.60'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 10/23/95

Deborah D. Hedewald
907

Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M - 3 Corner common to Sections 1 & 12, T 8 N, R 15 W and Sections 6 & 7, T 8 N, R 14 W.
4" CIM
Ottawa County Remonumentation tag and nail in W. Side 26" Spruce N 39° E 53.03'
Ottawa County Remonumentation tag and nail in E. Side P.P. S 150° W 119.95'
Ottawa County Remonumentation tag and nail in E. Side P.P. N 100° W 185.52'
Ottawa County Remonumentation tag and nail in S. Side P.P. N 78° E 245.00'

Signed by Carl P. Englert Jr.
Surveyor's Michigan License No. 18987

Date 10/17/1995



A - 3 Polkton Twp. T 8 N, R 14 W
M - 3 Crockery Twp. T 8 N, R 15 W
LCRC Liber 4, Page 96 August 12, 1980.
Found 5/8" Iron Bar, Set CIM
St. Sign 43.4'
Fence Post SE 41.98'
18" Spruce NE 53.30'
Center of Telephone Pedestal NW 40.60'

\$ 11.00 CORNER