

SURVEY & REMONUMENTATION

APR 05 1996

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

COMMISSION

For corners in

Ottawa

(County)

Located In:

Corner Code \neq

Crockery Twp.

- | | | |
|------------------------------------|----------------------------|------------------------|
| 1. Public Land Survey | T <u>8</u> N R <u>15</u> W | M - 6 |
| | T _____ R _____ | E $\frac{1}{4}$ Corner |
| | T _____ R _____ | Section 13 |
| | T _____ R _____ | |
| 2. Property Controlling in Section | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |

RECORDED

95 NOV 15 PM 2:05

Richard C. Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Carl P. Englert, Jr., in a field survey on October 9, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

M - 6 $\frac{1}{4}$ corner common to Section 13, T 8 N, R 15 W & Section 18, T 8 N, R 14 W.
Original corner set March 1837 by John Mullett D.S.
Set $\frac{1}{4}$ Section Post
Ironwood 8" S 5° W 48 Links
Leynn 12" N 21° W 24 Links
LCRC Liber 4, Page 98
August 12, 1980
Fd. Iron Pipe, Set CIM
P.P. West 90.42'
P.P. SW 305.34
"X" in E. End Conc Culvert
NE 262.68

see other side

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M - 6 $\frac{1}{4}$ corner common to Section 13, T 8 N, R 15 W & Section 18, T 8 N, R 14 W.
Found 4" CIM in Mon Box CL of Asphalt Road
Found P.P. West 90.43'
Found P.P. SW 305.34'

RA. 345 OTTAWA COUNTY
PEER APPROVED 10/23/95

Keddy D. Nedeweld
PDN

Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M - 6 $\frac{1}{4}$ corner common to Section 13, T 8 N, R 15 W & Section 18, T 8 N, R 14 W.
4" CIM in Mon Box
Ottawa County Remonumentation Tag and Nail in N. side P.P. S 87° W 90.40'
Ottawa County Remonumentation Tag and Nail in NW side P.P. S 17° W 305.29'
Ottawa County Remonumentation Tag and Nail in E. side P.P. N 17° W 312.16'
Ottawa County Remonumentation Tag and Nail in E side 11" Maple N 18° E 445.40'

Signed by Carl P. Englert Jr. Date 10/17/1995
Surveyor's Michigan License No. 18987



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

A - 6 Polkton Twp T 8 N, R 14 W
M - 6 Crockery Twp T 8 N, R 15 W
LCRC Liber 5, Page 326
Fd CIM, Raised with new CIM
P.P. W 90.43'
6" App E 38.14'
P.P. SW 45.45'
P.P. SW 305.34'
15" Maple SE 98.25'
"X" E. End Conc. Culvert 262.68'

\$ 11.00 CORNER