

RECORDED
REMONUMENTATION

FEB 18 1994

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

93 NOV -8 PH 1:52

Phyllis D. ...
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

Ottawa COMMISSION
(County)

Located In: Crockery Twp. Corner Code #

1. Public Land Survey	T	8N	R	15W	M-7, N.E. cor-
	T		R		ner, Sec. 24
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Carl P. Englert Jr.

I, _____, in a field survey on July 9, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-7
L.C.R.C. Liber 4, Page 244, November 1981
Fd. 5/8" iron, Set cast iron monument
Telephone pole, N.NE. 84.16'
Power Pole, NW 71.84'
Telephone Pole, S.SE. 32.85'
Centerline Old U.S. 16, S. 31.95'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-7
Fd. 4" Harrison Monument in Monument Box
Centerline Cleveland St., S. 32.0'
P.P., NW 71.84'
On centerline of 96th Ave.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-7
Set O.C. Remon Cap in concrete over 4" Harrison Monument in monument box
O.C. Remon. Tag & Nail in SW side P.P., N 40 degrees W 72.23'
O.C. Remon. Tag & Nail in NE side cut-off Tel.P., S 15 degrees E 136.16'
O.C. Remon. Tag & Nail in W side Tel.P. S 07 degrees W 174.27'
O.C. Remon. Tag & Nail in P.P., S 32 degrees W 255.43'
Centerline Cleveland Street, S 32.00'

(E.D.M.)

Signed by Carl P. Englert Jr.
Surveyor's Michigan License No. 18987

Date October 6, 1993

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

