

OTTAWA COUNTY REMONUMENTATION

RECORDED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

93 DEC 15 AM 9:31

Register of Deeds
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
	<u>Crockery Township</u>	
1. Public Land Survey	T <u>8N</u> R <u>15W</u>	<u>M-9</u>
	T _____ R _____	<u>SE corner</u>
	T _____ R _____	<u>Section 24</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Carl P. Englert Jr.

I, _____, in a field survey on August 5, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-9 L.C.R.C., Liber 6, Page 245 (1-25-1993) Fd. C.I.M. in centerline N&S gravel road & 3'± N of centerline of gravel road East N 49 degrees E 46.35' N&S in SE side 8" Oak N 20 degrees W 55.58' N&S in NE side 12" Maple S 22 degrees E 24.96', NW Cor. Conc. Headwall S 33 degrees W 23.91', NE Cor. Conc. Headwall N 82 degrees W 12.97', Face of N leg signpost	L.C.R.C., Liber 4, Page 104 (10-14-1980) Fd. 1" Iron, Set C.I.M. 6" Cherry, NE 62.21' 9" Tree, NW 55.47' Centerline St. Sign, W 12.51' NW Cor. Conc. Headwall 24.97'
---	--


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-9 Found 4" Harrison monument 8" deep and accepted as a careful and faithful perpetuation of the position of the original corner.	N 82 degrees W 12.97', face of N leg of signpost S 22 degrees E 24.96', NW cor. conc. headwall S 33 degrees W 23.91', ne cor. conc. headwall N 20 degrees W 55.58', 12" Maple (14" Ash
---	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-9 4" Harrison cast iron monument
O.C. Remon. Tag & Nail in SE side 5" Oak, N 45 degrees E 56.32'
O.C. Remon. Tag & Nail in NE side 14" Ash, N 20 degrees W 55.10'
NW corner of concrete headwall, S 22 degrees E 24.96'
NE corner of concrete headwall, S 33 degrees W 23.91'
Face of N leg of sign post, N 82 degrees W 12.97'

(Tape)



Signed by Carl P. Englert Jr.
Surveyor's Michigan License No. 18987

Date December 3, 1993