

RECORDED

OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

96 DEC 18 PM 4:55

*D. P. Engert*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in

Ottawa

(County)

Located in: Crockery Township  
Corner Code #

- 1. Public Land Survey T8N R15W M-13  
T R SE Corner  
T R Section 36  
T R
- 2. Property Controlling in Section S T R  
S T R
- 3. Miscellaneous Property In Sec. S T R  
S T R

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Carl P. Engert, in a field survey on 9/3, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-13 S.E. Corner Section 36  
G.L.O. 1837 by John Mullett  
Set Post Corner Towns 7 & 8 North  
and Ranges 14 & 15 West  
Pine 20" dia. bears S52°E 7 links  
Hemlock 10" bears N82°W 24 links

LCRC Liber 1, Page 637 Sept. 1972  
Found Concrete Monument  
S.W. 12.67' 14" Pine  
S.E. 14.47' 18" Pine  
N.E. 27.46' 4" Cherry

See Other Side

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-13 S.E. Corner Section 36  
Found Cast Iron Monument  
Found S.W. 12.67' 14" Pine  
Found S.E. 14.47' 8" Pine  
Found N.E. 27.46' 4" Cherry

P.A. 345 OTTAWA COUNTY  
PEER APPROVED 12-9-96

*C. P. Engert*

Accepted as a careful and faithful perpetuation of the original position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-13  
S.E. Corner Section 36  
4" Harrison Cast Iron Monument 1" deep  
O.C. Remon tag & nail in E. Side 18" Pine S25°W 12.49'  
O.C. Remon tag & nail in N. Side 12" Spruce S88°E 19.73'  
O.C. Remon tag & nail in E. Side 12" Cherry N20°E 27.39'  
O.C. Remon tag & nail in N.E. Side Tw. 8" Pine N50°W 24.50'

Signed by Carl P. Engert  
Surveyor's Michigan License No. 18987

Date 12/18/96



M-13 Section corner common to Section 31, T8N, R14W, Section 36, T8N, R15W, Section 1, T7N, R15W & Section 6, T7N, R14W

LCRC Liber 4, Page 232 Oct. 1981

Set Cast Iron Monument

8" Pine S.E. 14.52'

16" Pine S.W. 12.57'

6" Cherry N.N.E. 27.43'

7" Spruce E.N.E. 22.5'

LCRC Liber 5, Page 317 May 1988

Found C.I. Monument

Found Spike in E. Side 16" Pine S.W. 12.6'

Found Spike in N.E. Side 4" Pine S.E. 14.49'

Found Spike in E. Side 6" W. Cherry N.N.E. 27.44'

Found Spike in S. Side 8" Spruce E.N.E. 22.49'