

SURVEY & REMONUMENTATION

DEC 01 1998

SECTION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T 8 N R 16 W	C-6
	T _____ R _____	_____
	T _____ R _____	West 1/4 corner
	T _____ R _____	Section 17
2. Property Controlling in Section	S _____ T _____ R _____	Spring Lake Twp
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECORDED

98 JUL 24 PM 1:47

Harry S. Hallock
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Steve Lampen, in a field survey on May 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18	17		16		15		14		13			
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-6 No information

GLO - Mullett - 1837
40.00 set quarter section post
Pine 10 S 1 E 4.68
No other

PA. 3-15 OTTAWA COUNTY
DEED APPROVED 6-15-98
M.D.N.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-6

Found no field evidence or survey record that the original GLO quarter section post had ever been located since the original GLO survey.

Calculated the position of C-6 mid-way and on line between C-5 and C-7.

Calculated position of C-6 is in a large active sand mining operation.

See sketch on back.

Calculated position of C-6 is accepted as a careful and faithful re-establishment of the position of the original corner.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-6

Calculated position

Azimuth = Michigan State Plane Grid direction

Remonumentation tag in West side	14" Oak	356° 24'	814.69
Remonumentation tag in West side	20" Oak	354° 08'	722.29
Remonumentation tag in South side	32" Ash	295° 19'	563.66
Remonumentation tag in North side	6" Poplar	283° 31'	555.10



Signed by Steven Lampen

Date July 20, 1998

Surveyor's Michigan License No. 37279

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1976
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993



SURVEY &
REMONUMENTATION

DEC 01 1998

SECTION

SECTION
18

SECTION
17

