

RECORDED

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

97 JUL 24 PM 2:25

For corners in

Ottawa
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 8N R 16W D-5
T R N 1/4 corn. Sect. 17
T R Spring Lake Twp
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

Elizabeth Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Thomas E. Joiner, in a field survey on April 7, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-5 Spring Lake Township	Liber 2, Page 249	Liber 2, Page 697
April 3, 1837	Found Concrete Monument	Found Concrete Monument
Calvin Britain D.S.	NNE 17.7' 15" Pine	Power Pole N 5° W 66.65 feet
Set Quarter Section Post	ENE 8.65' 7" Pine	16" Pine N 5° E 16.92 feet
Hemlock 7" N8°E 10 Links	W 45.45' 8" Pine	26" Oak S10° E 75.86 feet
Black Oak 16" S 13° W 40 Links		Power Line W 14.3± feet

SEE REVERSE SIDE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-5 Spring Lake Township
Found cast iron monument and accepted as a careful and faithful perpetuation of the position of the original corner.

Liber 3 Page 400	Liber 2 Page 697	Liber 2 Page 249
Cast Iron Monument	Found Concrete Monument	Found Concrete Monument
Triple 9" Maple SE 85.43'	26" Oak S 10° E 75.86	ENE 8.65 7" Pine
26" White Oak SE 75.88'		
NE Corner Block Foundation		
W, SW 79.14'		

PA. 345 OTTAWA COUNTY
PEER APPROVED 4-21-97

T.E. Joiner



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-5 Spring Lake Township		
Cast Iron Monument		
Ottawa County Remon. tag and nail in N side	5" Black Cherry	AZ 294° Dist. 79.92'
Ottawa County Remon. tag and nail in W side	9" Jack Pine	AZ 8° Dist. 43.95'
Ottawa County Remon. tag and nail in NW side	11" Jack Pine	AZ 70° Dist. 8.80'
Ottawa County Remon. tag and nail in W side	Power Pole	AZ 185° Dist. 2.69'

\$ 11.00 CORNER

Signed by Thomas E. Joiner Date 4-8-97
Surveyor's Michigan License No. 18435

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

A. continued

Liber 3 Page 400

Set Cast Iron Monument Inscribed "Section Corner"

Power Pole NNW 66.60

17" Red Oak NE 66.69

Triple 9" Maple SE 85.43

26" White Oak SE 75.88

NE Corn. Block Foundation WSW 79.14'